


STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐

APPLICATION FOR PERMIT TO DRILL				1. WELL NAME and NUMBER NBU 921-20F		
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				3. FIELD OR WILDCAT NATURAL BUTTES		
4. TYPE OF WELL Gas Well Coalbed Methane Well: NO				5. UNIT or COMMUNITIZATION AGREEMENT NAME NATURAL BUTTES		
6. NAME OF OPERATOR KERR-MCGEE OIL & GAS ONSHORE, L.P.				7. OPERATOR PHONE 720 929-6587		
8. ADDRESS OF OPERATOR P.O. Box 173779, Denver, CO, 80217				9. OPERATOR E-MAIL mary.mondragon@anadarko.com		
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU 0575		11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>		
13. NAME OF SURFACE OWNER (if box 12 = 'fee')				14. SURFACE OWNER PHONE (if box 12 = 'fee')		
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')				16. SURFACE OWNER E-MAIL (if box 12 = 'fee')		
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') Ute Tribe		18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>		19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
20. LOCATION OF WELL	FOOTAGES	QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN
LOCATION AT SURFACE	2124 FNL 2189 FWL	SE	20	9.0 S	21.0 E	S
Top of Uppermost Producing Zone	2124 FNL 2189 FWL	SE	20	9.0 S	21.0 E	S
At Total Depth	2124 FNL 2189 FWL	SE	20	9.0 S	21.0 E	S
21. COUNTY UINTAH		22. DISTANCE TO NEAREST LEASE LINE (Feet) 2124		23. NUMBER OF ACRES IN DRILLING UNIT 1600		
		25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 750		26. PROPOSED DEPTH MD: 10256 TVD: 10256		
27. ELEVATION - GROUND LEVEL 4793		28. BOND NUMBER WYB000291		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Permit #43-8496		

ATTACHMENTS**VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP
NAME Danielle Piernot	TITLE Regulatory Analyst
SIGNATURE	DATE 12/01/2009
PHONE 720 929-6156	EMAIL danielle.piernot@anadarko.com
API NUMBER ASSIGNED 43047508350000	APPROVAL  Permit Manager

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	10256		
Pipe	Grade	Length	Weight			
	Grade HCP-110 LT&C	656	11.6			
	Grade I-80 Buttress	9600	11.6			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	11	8.625	0	2595		
Pipe	Grade	Length	Weight			
	Grade I-80 LT&C	2595	28.0			

T9S, R21E, S.L.B.&M.

Found 2006
Aluminum Cap in
Pile of Stones

N89°58.7'W - 39.921 (G.L.O.)
N89°54'13"W - 2634.82' (Meas.)

N89°57.5'W - 40.129 (G.L.O.)
N89°53'24"W - 2648.44' (Meas.)

Found 2006
Aluminum Cap
with Set Stone
North of Cap

2657.29' (Measured)
N00°03'14"W (Basis of Bearings)

N0°08.0'W - 80.522 (G.L.O.)
N00°03'21"W - 2657.24' (Meas.)

Found 2006
Aluminum Cap in
Pile of Stones

2124'

2189'

Proposed Well

Found 2006
Aluminum Cap in
Pile of Stones

20

WELL LOCATION:
NBU 921-20F

ELEV. UNGRADED GROUND = 4792.9'

NBU 921-20F (Proposed Well Head)

NAD 83 LATITUDE = 40.023009° (40° 01' 22.831")
LONGITUDE = 109.577204° (109° 34' 37.933")
NAD 27 LATITUDE = 40.023044° (40° 01' 22.958")
LONGITUDE = 109.576514° (109° 34' 35.450")

N00°00'48"W - 2668.44' (Meas.)
N0°04.6'W - 40.429 (G.L.O.)

Found 2006
Aluminum Cap in
Pile of Stones

N00°02'18"E - 2636.94' (Meas.)
N0°01.7'W - 39.953 (G.L.O.)

Found 2006
Aluminum Cap in
Pile of Stones
under E-W Fence

N89°54'43"W - 2640.77' (Meas.)
N89°59.4'W - 40.011 (G.L.O.)

Found 2006
Aluminum Cap in
Pile of Stones
under E-W Fence

S89°55'12"W - 2636.26' (Meas.)
S89°51.2'W - 39.942 (G.L.O.)

Found 2006
Aluminum Cap in
Pile of Stones,
Under E/W Fence

NOTES:

▲ = Section Corners Located

- Well footages are measured at right angles to the Section Lines.
- G.L.O. distances are shown in feet or chains.
1 chain = 66 feet.
- Bearings are based on Global Positioning Satellite observations.
- Basis of elevation is Tri-Sta "Two Water" located in the NW $\frac{1}{4}$ of Section 1, T10S, R21E, S.L.B.&M. The elevation of this Tri-Sta is shown on the Big Pack Mtn NE 7.5 Min. Quadrangle as being 5238'.



SCALE

SURVEYOR'S CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION No. 362251
STATE OF UTAH

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-20F

NBU 921-20F
WELL PLAT
2124' FNL, 2189' FWL
SE $\frac{1}{4}$ NW $\frac{1}{4}$ OF SECTION 20, T9S, R21E,
S.L.B.&M., UTAH COUNTY, UTAH.



609 CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE

(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE SURVEYED: 04-15-09	SURVEYED BY: M.S.B.	SHEET NO: 1 1 OF 9
DATE DRAWN: 04-16-09	DRAWN BY: M.W.W.	
SCALE: 1" = 1000'	Date Last Revised: 08-28-09	

NBU 921-20F

Surface: 2,124' FNL 2,189' FWL (SE/4NW/4)
Sec. 20 T9S R21E

Uintah, Utah
Mineral Lease: UTU 0575
Surface Owner: Ute Indian Tribe
Operator: Kerr-McGee Oil & Gas Onshore LP

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. – 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 – Surface	
Green River	1,616'	
Birds Nest	1,885'	Water
Mahogany	2,391'	Water
Wasatch	4,968'	Gas
Mesaverde	7,987'	Gas
MVU2	8,957'	Gas
MVL1	9,498'	Gas
TD	10,256'	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program.

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program.

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program.

6. **Evaluation Program:**

Please refer to the attached Drilling Program.

7. Abnormal Conditions:

Maximum anticipated bottomhole pressure calculated at 10,256' TD, approximately equals 6,390 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 4,133 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found

competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12-1/4 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 12-1/4 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 9-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see

attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). The air rig operation utilizes a 5M BOPE when drilling. This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

10. Other Information:

Please refer to the attached Drilling Program.

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP				DATE	November 30, 2009			
WELL NAME	NBU 921-20F				TD	10,256' MD/TVD			
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah		FINISHED ELEVATION	4,792'
SURFACE LOCATION	SE/4 NW/4	2,124' FNL	2,189' FWL	Sec 20	T 9S	R 21E	BHL		Straight Hole
	Latitude: 40.023009		Longitude: 109.577204		NAD 83				
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: BLM (MINERALS), Ute Tribe (SURFACE), UDOGM, Tri-County Health Dept.								

NBU 921-20F-Vertical well-Greater than 9650' TVD-updated 112009.xls



KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3,390	1,880	348,000
SURFACE	8-5/8"	0 to 2595	28.00	IJ-55	LTC	0.80*	1.55	4.79
						7,780	6,350	278,000
PRODUCTION	4-1/2"	0 to 9600	11.60	I-80	BTC	1.83	1.04	2.87
						10,690	8,650	279,000
		9600 to 10256	11.60	HCP-110	LTC	2.52	1.33	45.07

*Burst on surface casing is controlled by fracture gradient as shoe with gas gradient above.

D.F. = 2.07

1) Max Anticipated Surf. Press.(MASP) (Surf Csg) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac grad x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 12.2 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MASP 4,133 psi

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 12.2 ppg)

0.62 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MABHP 6,390 psi

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	215	60%	15.60	1.18
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	260	0%	15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
			Premium cmt + 2% CaCl				
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized					
Option 2	LEAD	2,095'	Prem cmt + 16% Gel + 10 pps gilsonite	190	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOC				
	TAIL	500	Premium cmt + 2% CaCl	150	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	4,466'	Premium Lite II + 0.25 pps celloflake +	360	40%	11.00	3.38
			5 pps gilsonite + 10% gel '+' 1% Retarder				
	TAIL	5,790'	50/50 Poz/G + 10% salt + 2% gel	1,420	40%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint for a total of 15 bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Emile Goodwin


DATE:

DRILLING SUPERINTENDENT:


John Merkel / Lovel Young

DATE:


EXHIBIT A
NBU 921-20F



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



CROSS SECTION A-A'



CROSS SECTION B-B'

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-20F

WELL PAD - CROSS SECTIONS

NBU 921-20F

2124' FNL, 2189' FWL

SE1/4 NW1/4 OF SECTION 20, T9S, R21E
S.L.B.&M., UINTAH COUNTY, UTAH



CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

Scale: 1"=100'

Date: 4/22/09


SHEET NO:

3

3 OF 9

REVISED:

RAW
9/1/09



TIMBERLINE
ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

(435) 789-1365




PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: SOUTHEASTERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: EASTERLY

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street - Denver, Colorado 80202

Well Pad - NBU 921-20F

NBU 921-20F
LOCATION PHOTOS
2124' FNL, 2189' FWL
SE $\frac{1}{4}$ NW $\frac{1}{4}$ OF SECTION 20, T9S, R21E,
S.L.B.&M., UINTAH COUNTY, UTAH.




CONSULTING, LLC
371 Coffeen Avenue
Sheridan WY 82801
Phone 307-674-0609
Fax 307-674-0182

TIMBERLINE

(435) 789-1365

ENGINEERING & LAND SURVEYING, INC.
209 NORTH 300 WEST - VERNAL, UTAH 84078

DATE PHOTOS TAKEN: 04-15-09	PHOTOS TAKEN BY: M.S.B.	SHEET NO: 4 4 OF 9
DATE DRAWN: 04-16-09	DRAWN BY: M.W.W.	
Date Last Revised: 08-28-09		



Legend

- Proposed NBU 921-20F Well Location
- Access Route - Proposed

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

Well Pad - NBU 921-20F

NBU 921-20F

Topo A

2124' FNL, 2189' FWL

SE¼ NW¼, Section 20, T9S, R21E

S.L.B.&M., Uintah County, Utah



CONSULTING, LLC
371 Coffeen Avenue
Sheridan, WY 82801
Phone (307) 674-0609
Fax (307) 674-0182




Scale: 1:100,000	NAD83 USP Central
Drawn: JELO	Date: 13 Apr 2009
Revised: TL	Date: 31 Aug 2009

Sheet No:

5

5 of 9



Legend

- Well - Proposed
- Well Pad
- Road - Proposed
- Road - Existing

Total Proposed Road Length: ±2,045ft

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

Well Pad - NBU 921-20F

NBU 921-20F

Topo B


2124' FNL, 2189' FWL

SE¼ NW¼, Section 20, T9S, R21E

S.L.B.&M., Uintah County, Utah



Scale: 1" = 2,000ft	NAD83 USP Central	Sheet No:
Drawn: JELO	Date: 13 Apr 2009	6 6 of 9
Revised: TL	Date: 31 Aug 2009	



Legend

- | | | | | |
|---|---|--|--|--|
| ● Well - Proposed | Well - 1 Mile Radius | ● Producing | ✕ Location Abandoned | ● Shut-In |
| Well Pad | | ▲ Approved permit (APD); not yet spudded | ● Temporarily-Abandoned | |
| | | ○ Spudded (Drilling commenced; Not yet complete) | ● Plugged and Abandoned | |

Kerr-McGee Oil & Gas Onshore, LP
1099 18th Street, Denver, Colorado 80202

Well Pad - NBU 921-20F

NBU 921-20F

Topo C


2124' FNL, 2189' FWL

SE¼ NW¼, Section 20, T9S, R21E

S.L.B.&M., Uintah County, Utah



Scale: 1" = 2,000ft	NAD83 USP Central	Sheet No:
Drawn: JELO	Date: 13 Apr 2009	7
Revised: TL	Date: 31 Aug 2009	7 of 9



Legend

- Well - Proposed
- Well Pad
- Pipeline - Proposed
- Road - Proposed
- Pipeline - Existing
- Road - Existing

Proposed Pipeline Length From Tie-In Point To Edge Of Pad: $\pm 1,675$ ft
 Proposed Pipeline Length Around Pad: ± 660 ft

Kerr-McGee Oil & Gas Onshore, LP
 1099 18th Street, Denver, Colorado 80202

Well Pad - NBU 921-20F

NBU 921-20F

Topo D

2124' FNL, 2189' FWL

SE¼ NW¼, Section 20, T9S, R21E

S.L.B.&M., Uintah County, Utah



Scale: 1" = 2,000ft	NAD83 USP Central	Sheet No:
Drawn: JELO	Date: 13 Apr 2009	8
Revised: TL	Date: 31 Aug 2009	

8 of 9

Kerr-McGee Oil & Gas Onshore, LP
WELL PAD - NBU 921-20F
WELL – NBU 921-20F
Section 20, T9S, R21E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 13.9 MILES TO THE JUNCTION OF STATE HIGHWAY 88. EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION ALONG STATE HIGHWAY 88 APPROXIMATELY 16.8 MILES TO OURAY, UTAH. FROM OURAY, PROCEED IN A SOUTHERLY DIRECTION ALONG THE SEEP RIDGE ROAD (COUNTY B ROAD 2810) APPROXIMATELY 5.3 MILES TO THE INTERSECTION OF A SERVICE ROAD TO THE EAST. EXIT LEFT AND PROCEED IN A NORTHEASTERLY THEN SOUTHEASTERLY DIRECTION ALONG THE SERVICE ROAD APPROXIMATELY 5.1 MILES TO A SECOND SERVICE ROAD TO THE NORTHEAST. EXIT LEFT AND PROCEED IN A NORTH BY NORTHEAST DIRECTION ALONG THE SECOND SERVICE ROAD APPROXIMATELY 0.8 MILES TO THE PROPOSED ACCESS ROAD. FOLLOW ROAD FLAGS IN A NORTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 2,045 FEET TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE WELL LOCATION IS APPROXIMATELY 42.3 MILES IN A SOUTHERLY DIRECTION.

NBU 921-20F

Surface: 2,124' FNL 2,189' FWL (SE/4NW/4)
Sec. 20 T9S R21E

Uintah, Utah
Mineral Lease: UTU 0575
Surface Owner: Ute Indian Tribe
Operator: Kerr-McGee Oil & Gas Onshore LP

ONSHORE ORDER NO. 1

***MULTI-POINT SURFACE USE & OPERATIONS PLAN
SUBMITTED WITH SITE-SPECIFIC INFORMATION***

This Application for Permit to Drill (APD) is filed under the Notice of Staking (NOS) process as stated in Onshore Order No. 1 (OSO #1) and supporting Bureau of Land Management (BLM) and Bureau of Indian Affairs (BIA) documents. An NOS was submitted showing the surface location in SE/4 NW/4 of Section 20 T9S R21E.

This Surface Use Plan of Operations (SUPO) or 13-point plan provides the site-specific information for the above-referenced wells. This information is to be incorporated by reference into the Master Development Plan (MDP) for Kerr-McGee Oil & Gas Onshore LP (Kerr-McGee). The MDP is available upon request from the BIA-Ft Duchesne Office.

An on-site meeting was held on September 1, 2009. Present were:

- Verlyn Pindell, Dave Gordon – BLM;
- Bucky Secakuku – BIA
- Bradley Pinnecoose – Ute Indian Tribe
- Scott Carson – Smiling Lake Consulting, Inc.
- Kolby Kay, Mitch Batty – 609 Consulting, LLC
- Nick Hall – Grasslands Consulting, Inc.
- Hal Blanchard, Charles Chase, Tony Kazeck and Raleen White – Kerr-McGee.

1. Existing Roads:

- A) Refer to Topo Map A for directions to the location.
- B) Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

2. Planned Access Roads:

See MDP for additional details on road construction.

Approximately $\pm 2,045'$ (± 0.39 miles) of new access road is proposed. Please refer to the attached Topo Map B. No pipelines will be crossed with the new construction.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site and are typically shown on the attached Exhibits and Topo maps.

3. **Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

4. **Location of Existing and Proposed Facilities:**

See MDP for additional details on Existing and Proposed Facilities.

The following guidelines will apply if the well is productive.

Approximately $\pm 2,335'$ (± 0.44 miles) of pipeline is proposed. Please refer to Topo D for the existing pipeline. Appropriate surface use agreements have been or will be obtained from the Ute Indian Tribe. Pipeline segments will be welded or zaplocked together on disturbed areas in or near the location, whenever possible, and dragged into place

Based on the comments from the onsite, Kerr-McGee has agreed to the following:

- Construct a low-water crossing on access road
- Re-route the washes around the well pad
- Arch Monitor
- Raptor Survey to ensure the existing nest to the north of the pad is not active

5. **Location and Type of Water Supply:**

See MDP for additional details on Location and Type of Water Supply.

Water for drilling purposes will be obtained from one of the following sources:

- Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.
- Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

No water well is to be drilled on this lease.

6. **Source of Construction Materials:**

See MDP for additional details on Source of Construction Materials.

7. **Methods of Handling Waste Materials:**

See MDP for additional details on Methods of Handling Waste Materials.

Any produced water from the proposed well will be contained in a water tank and will then be hauled by truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E
NBU #159 in Sec. 35 T9S R21E
Ace Oilfield in Sec. 2 T6S R20E
MC&MC in Sec. 12 T6S R19E
Pipeline Facility in Sec. 36 T9S R20E
Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E
Bonanza Evaporation Pond in Sec. 2 T10S R23E

8. Ancillary Facilities:

See MDP for additional details on Ancillary Facilities.

None are anticipated.

9. Well Site Layout: (See Location Layout Diagram)

See MDP for additional details on Well Site Layout.

All pits will be fenced according to the following minimum standards:

- Net wire (39-inch) will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.
- The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.
- Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.
- All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

10. Plans for Reclamation of the Surface:

See MDP for additional details on Plans for Reclamation of the Surface.

Kerr-McGee shall call the BIA for the seed mixture prior to starting interim and/or final reclamation actions.

11. Surface/Mineral Ownership:

The well pad and access road are located on lands owned by:

Ute Indian Tribe
PO Box 70
Fort Duchesne, Utah 84026
435-722-5141

The mineral ownership is listed below:

United States of America
Bureau of Land Management
170 South 500 East
Vernal, UT 84078
435-781-4400

12. Other Information:

See MDP for additional details on Other Information.

13. Lessee's or Operators' Representative & Certification:

Kathy Schneebeck Dulnoan
Staff Regulatory Analyst
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6007

Tommy Thompson
General Manager, Drilling
Kerr-McGee Oil & Gas Onshore LP
PO Box 173779
Denver, CO 80217-3779
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.


Kathy Schneebeck Dulnoan

November 30, 2009
Date

CLASS I REVIEW OF KERR-MCGEE OIL & GAS
ONSHORE LP'S 20 PROPOSED WELL LOCATIONS
(T9S, R21E, SEC. 8, 10, 11, 12, 17, 18, 19, AND 20)
IN UINTAH COUNTY, UTAH

By:

Patricia Stavish

Prepared For:

Ute Tribal Land
Uintah and Ouray Agency

Prepared Under Contract With:

Kerr-McGee Oil & Gas Onshore LP
1368 South 1200 East
Vernal, Utah 84078

Prepared By:

Montgomery Archaeological Consultants, Inc.
P.O. Box 219
Moab, Utah 84532

MOAC Report No. 09-39b

October 9, 2009

United States Department of Interior (FLPMA)
Permit No. 09-UT-60122

Ute Tribal Permit No. A09-363

IPC #09-81

Paleontological Reconnaissance Survey Report

**Survey of Kerr McGee's Proposed Well Pads, Access Roads,
and Pipelines for "NBU #921-18M, 18N, 19F, 20F, & 20H"
(Sec. 18-21, T 9 S, R 21 E)**

Ouray SE
Topographic Quadrangle
Uintah County, Utah

June 18, 2009

Prepared by Stephen D. Sandau
Paleontologist for
Intermountain Paleo-Consulting
P. O. Box 1125
Vernal, Utah 84078



Grasslands Consulting, Inc.

4800 Happy Canyon Road, Suite 110, Denver, CO 80237

(303) 759-5377 Office (303) 759-5324 Fax

SPECIAL STATUS PLANT AND WILDLIFE SPECIES REPORT

Report Number: GCI #95

Operator: Kerr-McGee Oil & Gas Onshore LP

Wells: NBU 921-20D (Bores: NBU 921-20D1CS, NBU 921-20D4BS, NBU 921-20D4CS, and NBU 921-20B3CS), NBU 921-20F, and NBU 921-20G

Pipeline: Associated pipelines leading to proposed well pads

Access Road: Associated access roads leading to proposed well pads

Location: Section 20, Township 9 South, Range 21 East; Uintah County, Utah

Survey-Species: Uinta Basin Hookless Cactus (*Sclerocactus wetlandicus*)

Date: June 16, June 25, and August 26, 2009

Observers: Grasslands Consulting, Inc. Biologists: Chris Gayer, Nick Hall, Dan Hamilton, Jonathan Sexauer, and Garrett Peterson.

Weather: Partly cloudy, 80-90°F, 0-5 mph winds with no precipitation.

API Number: 4304750835

Well Name: NBU 921-20F




Township 09.0 S Range 21.0 E Section 20

Meridian: SLBM

Operator: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Map Prepared:

Map Produced by Diana Mason



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

December 4, 2009

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2009 Plan of Development Natural Buttes Unit
Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2009 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-50831	NBU 922-32M1AS	Sec 32 T09S R22E 1160 FSL 2283 FWL
	BHL	Sec 32 T09S R22E 1128 FSL 1074 FWL
43-047-50832	NBU 922-32M1CS	Sec 32 T09S R22E 1147 FSL 2268 FWL
	BHL	Sec 32 T09S R22E 0872 FSL 0726 FWL
43-047-50833	NBU 922-32N4AS	Sec 32 T09S R22E 1187 FSL 2313 FWL
	BHL	Sec 32 T09S R22E 0554 FSL 2572 FWL
43-047-50834	NBU 922-32N4CS	Sec 32 T09S R22E 1174 FSL 2299 FWL
	BHL	Sec 32 T09S R22E 0310 FSL 2234 FWL
43-047-50835	NBU 921-20F	Sec 20 T09S R21E 2124 FNL 2189 FWL
43-047-50836	NBU 921-20G	Sec 20 T09S R21E 1684 FNL 2530 FEL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Natural Buttes Unit
Division of Oil Gas and Mining
Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:12-4-09

WORKSHEET

APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 12/1/2009

API NO. ASSIGNED: 43047508350000

WELL NAME: NBU 921-20F

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995)

PHONE NUMBER: 720 929-6156

CONTACT: Danielle Piernot

PROPOSED LOCATION: SENW 20 090S 210E

Permit Tech Review: ☒

SURFACE: 2124 FNL 2189 FWL

Engineering Review: ☒

BOTTOM: 2124 FNL 2189 FWL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.02292

LONGITUDE: -109.57643

UTM SURF EASTINGS: 621480.00

NORTHINGS: 4431061.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU 0575

PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

SURFACE OWNER: 2 - Indian

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ **PLAT**

☒ **Bond:** FEDERAL - WYB000291

☐ **Potash**

☒ **Oil Shale 190-5**

☐ **Oil Shale 190-3**

☐ **Oil Shale 190-13**

☒ **Water Permit:** Permit #43-8496

☐ **RDCC Review:**

☐ **Fee Surface Agreement**

☒ **Intent to Commingle**

Commingle Approved

LOCATION AND SITING:

☐ **R649-2-3.**

Unit: NATURAL BUTTES

☐ **R649-3-2. General**

☐ **R649-3-3. Exception**

☒ **Drilling Unit**

Board Cause No: Cause 173-14

Effective Date: 12/2/1999

Siting: 460' fr u bdry & uncomm. tract

☐ **R649-3-11. Directional Drill**

Comments: Presite Completed

Stipulations: 3 - Commingle - ddoucet
4 - Federal Approval - dmason
17 - Oil Shale 190-5(b) - dmason

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute Tr
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
PHONE NUMBER: 720 929-6007 Ext		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/29/2010 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 12/30/2010

By:

NAME (PLEASE PRINT) Danielle Piernot	PHONE NUMBER 720 929-6156	TITLE Regulatory Analyst
SIGNATURE N/A		DATE 12/29/2010



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047508350000

API: 43047508350000

Well Name: NBU 921-20F

Location: 2124 FNL 2189 FWL QTR SENW SEC 20 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 12/28/2009

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Approved by the
Utah Division of
Oil, Gas and Mining

Signature: Danielle Piernot

Date: 12/29/2010

Title: Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE,

Date: 12/30/2010

By: 

RECEIVED December 29, 2010

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

DEC 8 2009
mc

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

BLM

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU0575
1b. Type of Well: <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator KERRMCGEE OIL&GAS ONSHORE LP Contact: DANIELLE E PIERNOT Email: Danielle.Piernot@anadarko.com		7. If Unit or CA Agreement, Name and No. 891008900A
3a. Address PO BOX 173779 DENVER, CO 80202-3779		8. Lease Name and Well No. NBU 921-20F
3b. Phone No. (include area code) Ph: 720-929-6156 Fx: 720-929-7156		9. API Well No. 43 047 50835
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SENW 2124FNL 2189FWL 40.02301 N Lat, 109.57720 W Lon At proposed prod. zone SENW 2124FNL 2189FWL 40.02301 N Lat, 109.57720 W Lon		10. Field and Pool, or Exploratory NATURAL BUTTES
14. Distance in miles and direction from nearest town or post office* APPROXIMATELY 11 MILES SOUTHEAST OF OURAY, UTAH		11. Sec., T., R., M., or Blk. and Survey or Area Sec 20 T9S R21E Mer SLB
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 2124 FEET	16. No. of Acres in Lease 1600.00	12. County or Parish UINTAH
17. Spacing Unit dedicated to this well	18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. APPROXIMATELY 750 FEET	13. State UT
19. Proposed Depth 10256 MD 10256 TVD	20. BLM/BIA Bond No. on file WYB000291	21. Elevations (Show whether DF, KB, RT, GL, etc.) 4793 GL
22. Approximate date work will start 12/28/2009	23. Estimated duration 60-90 DAYS	

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) DANIELLE E PIERNOT Ph: 720-929-6156	Date 12/04/2009
Title REGULATORY ANALYST I		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date NOV 07 2011
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #78398 verified by the BLM Well Information System
For KERRMCGEE OIL&GAS ONSHORE LP, sent to the Vernal
Committed to AFMSS for processing by GAIL JENKINS on 12/08/2009 ()

RECEIVED

NOV 18 2011

DIV. OF OIL, GAS & MINING

NOTICE OF APPROVAL

UDOGM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

106XJ0969AE

NO NCS



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Kerr McGee Oil & Gas Onshore
Well No: NBU 921-20F
API No: 43-047-50835

Location: Sec. 20, T9S, R21E
Lease No: UTU-0575
Agreement: Natural Buttes Unit

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Construction Activity (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	- Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig.
Spud Notice (Notify BLM Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: BLM_UT_VN_OpReport@blm.gov .
BOP & Related Equipment Tests (Notify BLM Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify BLM Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- Paint facilities "Shadow Gray."
- Re-route ephemeral drainages around perimeter of the well pad.
- Construct low water crossing on access road at ephemeral wash.
- Monitor location by a permitted archaeologist during the construction process.
- Monitor location by a permitted paleontologist during the construction process.
- In accordance with the guidelines specified in the Utah BLM Field Office Guidelines for Raptor Protection from Human and Land Use Disturbances, 2002 a raptor survey shall be conducted prior to construction of the proposed location, pipeline, or access road if construction will take place during raptor nesting season (January 1 through September 30). If active raptor nests are identified during a new survey, KMG shall conduct its operations according to the seasonal restrictions detailed I the Uinta Basin-specific RMP guidelines and spatial offsets specified by the USFWS Utah Raptor Guidelines (See Appendix D). The USFWS recommends a ¼-mile avoidance buffer surrounding active burrowing owl nests between March 1 and August 31. The USFWS recommends a ¼-mile avoidance buffer surrounding active golden eagle nests between January 1 and August 31.
- Conduct a new biological survey in accordance with the guidelines specified in the USFWS Rare Plant Conservation Measures for Uinta Basin hookless Cactus and the 2008 BLM RMP ROD, to include a 300-foot buffer from proposed construction operations (See Appendix D), and conduct operations according to agency specifications and the requirements of the BO issued as a result of Section & USFWS consultation.

BIA Standard Conditions of Approval:

- Soil erosion will be mitigated by reseeding all disturbed areas.
- The gathering pipelines will be constructed to lie on the surface. The surface pipelines will not be bladed or cleared of vegetation. Where pipelines are constructed parallel to roads they may be welded on the road and then lifted from the road onto the right-of-way. Where pipelines do not parallel roads but cross-country between sites, they shall be welded in place at well sites or on access roads and then pulled between stations with a suitable piece of equipment. Traffic will be restricted along these areas so that the pipeline right-of-way will not be used as an access road.

- An open drilling system shall be used, unless otherwise specified in 10.0 Additional Stipulations of this document and in the Application for Permit to Drill. A closed drilling system shall be used in all flood plain areas, and other highly sensitive areas, recommended by the Ute Tribe Technician, BIA, and other agencies involved.
- The reserve pit shall be lined with a synthetic leak proof liner. After the drilling operation is complete, excess fluids shall be removed from the reserve pit and either hauled to an approved disposal site or shall be used to drill other wells. When the fluids are removed the pit shall be backfilled a minimum of 3.0' below the soil surface elevation.
- A closed production system shall be used. This means all produced water and oil field fluid wastes shall be contained in leak proof tanks. These fluids shall be disposed of in either approved injection wells or disposal pits.
- Major low water crossings will be armored with pit run material to protect them from erosion.
- All personnel shall refrain from collecting any paleontological fossils and from disturbing any fossil resources in the area.
- If fossils are exposed or identified during construction, all construction must cease and immediate notification to the Energy and Minerals Department and the Cultural Rights Protection Officer.
- Before the site is abandoned the company will be required to restore the right-of-way to near its original state. The disturbed area will be reseeded with desirable perennial vegetation. If necessary, the Bureau of Indian Affairs or Bureau of Land Management will provide a suitable seed mixture.
- Noxious weeds will be controlled on all surface disturbances within the project area. If noxious weeds spread from the project area onto adjoining land, the company will also be responsible for their control.
- If project construction operations are scheduled to occur after December 31, 2009, KMG shall conduct annual raptor surveys in accordance with the guidelines specified in the Utah Field Office Guidelines for Raptor Protection from Human and Land Use Disturbances, 2002. If active raptor nest are indentified during a new survey, KMG shall conduct its operations according to the seasonal restrictions detailed in the Uinta basin-specific RMP guidelines and spatial offsets specified by the USFWS Utah Raptor Gui9ldlines (See Appendix D).
- USFWS threatened and endangered plant and animal conservation measures will be followed, as appropriate to the species identified by the biological resource survey (See Appendix D).
- All personnel shall refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
- If artifacts or any culturally sensitive materials are exposed or identified during construction, all construction must cease and immediate notification to the Energy and Minerals Department and the Cultural Rights Protection Officer.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

A Gama Ray Log shall be run from TD to surface.

Variances Granted:

Air Drilling:

- Properly lubricated and maintained rotating head, variance granted to use a properly maintained and lubricated diverter bowl in place of a rotating head.
- Blooie line discharge 100' from the well bore, variance granted for blooie line discharge to be 45' from the well bore.
- Compressors located in the opposite direction from the blooie line a minimum of 100' from the well bore. Variance granted for two truck/trailer mounted air compressors located within 40 feet from the well bore and 60' from the blooie line.
- In lieu of mud products on location, Kerr McGee will fill the reserve pit with water for kill fluid.
- Automatic igniter. Variance granted for igniter due to there being no productive formations while drilling with air.
- FIT test. Variance granted due to well-known geology and problems that can occur with FIT test.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be

performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.


- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/28/2011 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you.		
Approved by the Utah Division of Oil, Gas and Mining Date: 01/03/2012 By: 		
NAME (PLEASE PRINT) Danielle Piernot		PHONE NUMBER 720 929-6156
SIGNATURE N/A		TITLE Regulatory Analyst
DATE 12/21/2011		



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047508350000

API: 43047508350000

Well Name: NBU 921-20F

Location: 2124 FNL 2189 FWL QTR SENW SEC 20 TWNP 090S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 12/28/2009

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☐ Yes ☒ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Danielle Piernot

Date: 12/21/2011

Title: Regulatory Analyst **Representing:** KERR-MCGEE OIL & GAS ONSHORE, L.P.

RECEIVED Dec. 21, 2011

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: Uintah		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 3/13/2012	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU TRIPPLE A BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX. SPUD WELL ON 03/13/2012 AT 0800 HRS.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 16, 2012		
NAME (PLEASE PRINT) Sheila Wopsock	PHONE NUMBER 435 781-7024	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 3/15/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575			
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		9. FIELD and POOL or WILDCAT: NATURAL BUTTES			
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 3/15/2012 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The operator requests approval to deepen the well to the Blackhawk formation (part of the Mesaverde Group). The Operator also requests approval for closed loop drilling option, surface casing change and production casing change. All other aspects of the previously approved drilling plan will not change. Please see the attachment. Thank you.					
NAME (PLEASE PRINT) Jaime Scharnowske		PHONE NUMBER 720 929-6304			
SIGNATURE N/A		TITLE Regulatory Analyst			
DATE 3/15/2012		APPROVED BY THE UTAH DIVISION OF OIL, GAS AND MINING Date: March 26, 2012 By:			

Kerr-McGee Oil & Gas Onshore. L.P.**NBU 921-20F**

Surface: 2124 FNL / 2189 FEL SENW

Section 20 T9S R21E

Unitah County, Utah
Mineral Lease: UTU-0575**ONSHORE ORDER NO. 1****DRILLING PROGRAM**

1. & 2. **Estimated Tops of Important Geologic Markers:**
Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,608'	
Birds Nest	1,871'	Water
Mahogany	2,377'	Water
Wasatch	4,960'	Gas
Mesaverde	7,948'	Gas
Sego	10,233'	Gas
Castlegate	10,307'	Gas
Blackhawk	10,681'	Gas
TVD	11,281'	
TD	11,281'	

3. **Pressure Control Equipment** (Schematic Attached)

Please refer to the attached Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. **Drilling Fluids Program:**

Please refer to the attached Drilling Program

6. **Evaluation Program:**

Please refer to the attached Drilling Program

7. **Abnormal Conditions:**

Maximum anticipated bottom hole pressure calculated at 11281' TVD, approximately equals
7,445 psi (0.66 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 5,015 psi (bottom hole pressure
minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-
(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. **Anticipated Starting Dates:**

Drilling is planned to commence immediately upon approval of this application.

9. **Variances:**

Please refer to the attached Drilling Program.
Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

10. Other Information:

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	March 15, 2012		
WELL NAME	NBU 921-20F					TD	11,281'	TVD	11,281' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	FINISHED ELEVATION		4,792'
SURFACE LOCATION	SENW	2124 FNL	2189 FEL	Sec 20	T 9S	R 21E			
	Latitude:	40.023009	Longitude:	-109.577204		NAD 83			
OBJECTIVE ZONE(S)	BLACKHAWK (Part of the Mesaverde Group)								
ADDITIONAL INFO	Regulatory Agencies: BLM (Minerals), BIA (Surface), UDOGM Tri-County Health Dept.								

GEOLOGICAL			MECHANICAL		
LOGS	TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
<p>40'</p> <p>All water flows encountered while drilling will be reported to the appropriate agencies.</p> <p>Green River @ 1,608'</p> <p>Top of Birds Nest @ 1,871'</p> <p>Mahogany @ 2,377'</p> <p>Preset f/ GL @ 2,830' TVD</p> <p>Note: 11" surface hole will usually be drilled ±400' below the lost circulation zone (aka bird's nest). Drilled depth may be ±200' of the estimated set depth depending on the acutal depth of the loss zone.</p> <p>Wasatch @ 4,960'</p> <p>Mud logging program TBD</p> <p>Cased hole logging program from TD - surf csg</p> <p>Mverde @ 7,948' TVD</p> <p>Sego @ 10,233' TVD</p> <p>Castlegate @ 10,307' TVD</p> <p>MN5 @ 10,681' TVD</p> <p>Max anticipated Mud required 11,281' TVD</p> <p>13.0 ppg TD @ 11,281' MD</p>			<p>12 1/4"</p> <p>200'</p> <p>11'</p> <p>7-7/8"</p>	<p>14"</p> <p>8-5/8", 28#, IJ-55, LTC</p> <p>8-5/8", 28#, IJ-55, LTC</p> <p>4-1/2" 11.6# HCP-110 Ultra DQX/LTC csg</p>	<p>Air mist</p> <p>Air mist</p> <p>Water / Fresh Water Mud 8.3-13.0 ppg</p>

NBU 921-20F

Drilling Program
6 of 7

KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS			
						BURST	COLLAPSE	LTC	DQX
CONDUCTOR	14"	0-40'							
						3,390	1,880	348,000	N/A
SURFACE	8-5/8"	0 to 2,830	28.00	IJ-55	LTC	1.90	1.42	5.02	N/A
						10,690	8,650	279,000	367,000
PRODUCTION	4-1/2"	0 to 5,000	11.60	HCP-110	DQX	1.19	1.13		3.50
	4-1/2"	5,000 to 11,281'	11.60	HCP-110	LTC	1.19	1.13	4.78	

Surface Casing:

(Burst Assumptions: TD = 13.0 ppg)

0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 9000 psi)

0.66 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized					
Option 2	LEAD	2,330'	65/35 Poz + 6% Gel + 10 pps gilsonite	210	35%	11.00	3.82
			+ 0.25 pps Flocele + 3% salt BWOW				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	4,451'	Premium Lite II +0.25 pps	350	35%	12.00	3.38
			celloflake + 5 pps gilsonite + 10% gel				
			+ 0.5% extender				
	TAIL	6,830'	50/50 Poz/G + 10% salt + 2% gel	1,610	35%	14.30	1.31
			+ 0.1% R-3				

*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Nick Spence / Danny Showers / Chad Loesel


DATE:

DRILLING SUPERINTENDENT:

Kenny Gathings / Lovel Young

DATE:

RECEIVED: Mar. 15, 2012

EXHIBIT A
NBU 921-20F**SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK**

Requested Drilling Options:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one cuttings storage area to be constructed on the drilling pad or a traditional drilling operation with one pit used for drilling and completion operations. The cuttings storage area will be used to contain only the de-watered drill cuttings and will be lined and bermed to prevent any liquid runoff. The drill cuttings will be buried in the completion pit once completion operations are completed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit will be lined with a synthetic material 20 mil or thicker and will be used for the completing of the wells on the pad or used as part of our Aandarko Completions Transportation System (ACTS). Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completions pit.

If Kerr-McGee does not use a closed loop drilling system, it will construct a traditional drilling/completions pit to contain drill cuttings and for use in completion operations. The pit will be lined with a synthetic material 20 mil or thicker. The drill cuttings will be buried in the pit using traditional pit closure standards.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 3/21/2012	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 MIRU AIR RIG ON MARCH 18, 2012. DRILLED SURFACE HOLE TO 2,856'.
 RAN SURFACE CASING AND CEMENTED. WELL IS WAITING ON ROTARY RIG. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH WELL COMPLETION REPORT.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 March 26, 2012

NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regularatory Analyst
SIGNATURE N/A	DATE 3/22/2012	

BLM - Vernal Field Office - Notification Form

Operator KERR-McGEE OIL & GAS Rig Name/# BUCKET RIG
Submitted By J. Scharnowske Phone Number 720.929.6304
Well Name/Number NBU 921-20F
Qtr/Qtr SENW Section 20 Township 9S Range 21E
Lease Serial Number UTU-0575
API Number 4304750835

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 03/13/2012 08:00 HRS AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☒ Surface Casing
☐ Intermediate Casing
☐ Production Casing
☐ Liner
☐ Other

Date/Time 03/16/2012 08:00 HRS AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
☐ BOPE test at intermediate casing point
☐ 30 day BOPE test
☐ Other

RECEIVED**MAR 13 2012**

BUREAU OF OIL, GAS & MINERALS

Date/Time _____ AM ☐ PM ☐

Remarks ESTIMATED DATE AND TIME. PLEASE CONTACT KENNY GATHINGS AT

435.828.0986 OR LOVEL YOUNG AT 435.781.7051

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: KERR MCGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995
Address: 1368 SOUTH 1200 EAST
city VERNAL
state UT zip 84078 Phone Number: (435) 781-7024

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750835	NBU 921-20F		SENW	20	9S	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
B	99999	2900	3/13/2012			3/20/2012	
Comments: MIRU TRIPPLE A BUCKET RIG. WSMVD SPUD WELL ON 03/13/2012 AT 0800 HRS.							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA WOPSOCK

Name (Please Print)

Signature

REGULATORY ANALYST

Title

3/15/2012

Date

RECEIVED

MAR 15 2012

(5/2000)

Div. of Oil, Gas & Mining

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: Uintah		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 7/6/2012			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 No activity for the month of June 2012. Surface casing set at 2,856'.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 July 09, 2012

NAME (PLEASE PRINT) Jaime Scharnowske	PHONE NUMBER 720 929-6304	TITLE Regularatory Analyst
SIGNATURE N/A	DATE 7/6/2012	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
5. FIELD and POOL or WILDCAT: NATURAL BUTTES		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES		8. WELL NAME and NUMBER: NBU 921-20F
9. API NUMBER: 43047508350000		10. FIELD and POOL or WILDCAT: NATURAL BUTTES
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. No activity for the month of July 2012. Surface casing set at 2,871'.
TYPE OF SUBMISSION <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 8/2/2012	TYPE OF ACTION <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 07, 2012		
NAME (PLEASE PRINT) Cara Mahler		PHONE NUMBER 720 929-6029
SIGNATURE N/A		TITLE Regulatory Analyst I
DATE 8/2/2012		

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# PIONEER 54
Submitted By STUART NEILSON Phone Number 435-790-2921
Well Name/Number NBU 921-20F
Qtr/Qtr SE/NW Section 20 Township 9S Range 21E
Lease Serial Number UTU0575
API Number 4304750835

Casing – Time casing run starts, not cementing times.

- ☐ Production Casing
☐ Other

Date/Time _ _ AM ☐ PM ☐

BOPE

- ☒ Initial BOPE test at surface casing point
☐ Other

Date/Time 8/14/12 10:00 AM ☐ PM ☒

Rig Move

Location To:

Date/Time _____ AM ☐ PM ☐

Remarks _____

RECEIVED

AUG 14 2012

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
PHONE NUMBER: 720 929-6514		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: Uintah		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text" value="ACTS PIT"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/24/2012			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 FINISHED DRILLING TO 11929' ON 8/21/2012. RAN 4-1/2" 11.6# I-80 PRODUCTION CASING. CEMENTED PRODUCTION CASING. RELEASED PIONEER 54 RIG ON 8/24/2012. DETAILS OF CEMENT JOB WILL BE INCLUDED WITH THE WELL COMPLETION REPORT. WELL IS WAITING ON FINAL COMPLETION ACTIVITIES.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 August 24, 2012

NAME (PLEASE PRINT) Cara Mahler	PHONE NUMBER 720 929-6029	TITLE Regulatory Analyst I
SIGNATURE N/A	DATE 8/24/2012	

State of Utah - Notification Form

Operator Anadarko Petroleum Rig Name/# PIONEER 54
Submitted By STUART NEILSON Phone Number 435-790-2921
Well Name/Number NBU 921-20F
Qtr/Qtr SE/NW Section 20 Township 9S Range 21E
Lease Serial Number UTU0575
API Number 4304750835

Casing – Time casing run starts, not cementing times.

- ☒ Production Casing
☐ Other

Date/Time 8/23/12 6 AM ☒ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
☐ Other

Date/Time _ _ AM ☐ PM ☐

RECEIVED

AUG 22 2012

DIV. OF OIL, GAS & MINING

Rig Move

Location To: NBU 921-8D

Date/Time 8/24/12 7 AM ☒ PM ☐

Remarks _____

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
5. FIELD and POOL or WILDCAT: NATURAL BUTTES		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/2/2012	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Started completing the well. Well TD at 11,929.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 02, 2012		
NAME (PLEASE PRINT) Lindsey Frazier		PHONE NUMBER 720 929-6857
SIGNATURE N/A		TITLE Regulatory Analyst II
DATE 10/2/2012		

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU 0575
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: NBU 921-20F
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2124 FNL 2189 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 20 Township: 09.0S Range: 21.0E Meridian: S		9. API NUMBER: 43047508350000
5. FIELD and POOL or WILDCAT: NATURAL BUTTES		9. FIELD and POOL or WILDCAT: NATURAL BUTTES
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 10/16/2012	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> <p>The subject well was placed on production on 10/16/2012. The Chronological Well History will be submitted with the well completion report.</p> </div> <div style="width: 35%; text-align: center;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>FOR RECORD ONLY</p> <p>October 18, 2012</p> </div> </div>		
NAME (PLEASE PRINT) Lindsey Frazier		PHONE NUMBER 720 929-6857
SIGNATURE N/A		TITLE Regulatory Analyst II
DATE 10/18/2012		

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

5. Lease Serial No.
UTU0575

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.
UTU63047A8. Lease Name and Well No.
NBU 921-20F9. API Well No.
43-047-5083510. Field and Pool, or Exploratory
NATURAL BUTTES11. Sec., T., R., M., or Block and Survey
or Area Sec 20 T9S R21E Mer SLB12. County or Parish
UINTAH13. State
UT17. Elevations (DF, KB, RT, GL)*
4792 GL1a. Type of Well ☐ Oil Well ☒ Gas Well ☐ Dry ☐ Other
b. Type of Completion ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.
Other2. Name of Operator
KERR MCGEE OIL & GAS ONSHORE
Contact: LINDSEY A FRAZIER
Mail: lindsey.frazier@anadarko.com3. Address
PO BOX 173779
DENVER, CO 802173a. Phone No. (include area code)
Ph: 720-929-6857

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface SENW 2124FNL 2189FWL 40.023009 N Lat, 109.577204 W Lon

At top prod interval reported below SENW 2124FNL 2189FWL 40.023009 N Lat, 109.577204 W Lon

At total depth SENW 2124FNL 2189FWL 40.023009 N Lat, 109.577204 W Lon

14. Date Spudded
03/13/201215. Date T.D. Reached
08/21/201216. Date Completed
☐ D & A ☒ Ready to Prod.
10/16/201218. Total Depth: MD 11292
TVD 1128919. Plug Back T.D.: MD 11231
TVD 1122820. Depth Bridge Plug Set: MD
TVD21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
BHP-HDIL/ZDL/CNCR-CBL/GR/CCL/TEMP-GR/CBL22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit analysis)
Directional Survey? ☐ No ☒ Yes (Submit analysis)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
20.000	14.000 STL	36.7	0	40		28			
11.000	8.625 IJ-55	28.0	0	2840		1060		0	
7.875	4.500 P-110	11.6	0	11278		2290		20	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2.375	10742							

25. Producing Intervals

26. Perforation Record

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) MESAVERDE	8028	11061	8028 TO 11061	0.360	201	OPEN
B)						
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Depth Interval	Amount and Type of Material
8028 TO 11061	PUMP 13,309 BBLs SLICK H2O AND 318,480 LBS 30/50 OTTAWA SAND

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
10/16/2012	10/20/2012	24	→	0.0	3234.0	624.0			FLows FROM WELL
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
20/64	2392	2.0	→	0	3234	624		PGW	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

(See Instructions and spaces for additional data on reverse side)

ELECTRONIC SUBMISSION #160349 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	
			→						

29. Disposition of Gas(Sold, used for fuel, vented, etc.)
SOLD

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GREEN RIVER	1637
				BIRD'S NEST	1942
				MAHOGANY	2388
				WASATCH	4999
				MESAVERDE	8015

32. Additional remarks (include plugging procedure):

The first 210 ft of the surface hole was drilled with a 12 7/8 inch bit. The remainder of surface hole was drilled with an 11 inch bit. DQX P-110 csg was run from surface to 5037 ft; LTC P-110 csg was run from 5037 ft to 11,278 ft. A top down cement job using 440 sx cement was performed on 9/26/12 to get cement to surface. Attached is the chronological well history, perforation report & final survey. The rig release sn that was submitted 8/24/12 reported TD as 11,929; that was an error and should have reported TD as 11,292'.

33. Circle enclosed attachments:

- | | | | |
|---|--------------------|---------------|-----------------------|
| 1. Electrical/Mechanical Logs (1 full set req'd.) | 2. Geologic Report | 3. DST Report | 4. Directional Survey |
| 5. Sundry Notice for plugging and cement verification | 6. Core Analysis | 7. Other: | |

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

Electronic Submission #160349 Verified by the BLM Well Information System.
For KERR MCGEE OIL & GAS ONSHORE L, sent to the Vernal

Name (please print) LINDSEY A FRAZIERTitle REGULATORY ANALYSTSignature (Electronic Submission)Date 11/14/2012

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ** ORIGINAL ****

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
3/18/2012	13:00 - 18:30	5.50	MIRU	01	A	P		M.I.R.U / J.D. FIELD SERVICES, 2 TRUCKS 2 PERSONAL/ MOUNTAIN WEST OIL FIELD SERVICES, 1 TRUCK & (1) 1TON 3 PERSONAL/ PRO PETRO 10 HANDS / 100% MOVED / TRUCKS OFF LOCATION @ 18:00
	18:30 - 0:00	5.50	MIRU	01	B	P		MOVE TO NBU 922-30B4CS (WELL 4 OF 4) INSTALL DIVERTOR HEAD AND BLUEY LINE. BUILD DITCH. SPOT IN RIG. SPOT IN CATWALK AND PIPE RACKS. RIG UP PIT PUMP. RIG UP PUMP. PRIME PUMP. INSPECT RIG.
3/19/2012	0:00 - 1:30	1.50	MIRU	01	B	P		FINISH RIG UP ON NBU 921-20F (WELL 1 OF 1) TALLY INSPECTED DRILL STRING
	1:30 - 2:00	0.50	MIRU	08	B	Z		FIX SWEDGE ON PIT PUMP
	2:00 - 3:00	1.00	MIRU	06	A	P		PICK UP #1 BHA & DRILL STRING
	3:00 - 4:30	1.50	DRLSUR	02	D	P		DRL F/ 44' T/210' (166'@ 110.66' PER HR) WOB, 5-15K RPM 45 UP/DWN/ROT 20/20/20 PSI ON/OFF 600/400 M.W. 8.4# VIS 27
	4:30 - 5:00	0.50	DRLSUR	06	A	P		TOOH LDDP & BHA #1
	5:00 - 7:30	2.50	DRLSUR	06	A	P		POOH PU 11" BIT & DIR. TOOLS (AFTER INSPECTION)
	7:30 - 12:00	4.50	DRLSUR	02	D	P		DRL F/210' T/820' (610'@ 135.5 ' PER HR) WOB 20K RPM 45 UP/DWN/ROT 54/48/50 PSI ON/OFF 1100/800 M.W. 8.4# VIS 27
	12:00 - 0:00	12.00	DRLSUR	02	D	P		1' HIGH 2' LEFT OF TARGET DRL F/820' T/2200' (1380'@ 115 ' PER HR) WOB 20K RPM 45 UP/DWN/ROT 75/65/70 PSI ON/OFF 1660/1380 M.W. 8.4# VIS 27
3/20/2012	0:00 - 3:00	3.00	DRLSUR	02	D	P		1.27' LEFT .61' HIGH OF TARGET DRL F/2200' T/2380' (180'@ 51.4 ' PER HR) WOB 20K RPM 45 UP/DWN/ROT 77/66/72 PSI ON/OFF 1710/1420 M.W. 8.4# VIS 27
	3:00 - 18:00	15.00	DRLSUR	08	B	Z		HAVING TROUBLE WITH POWER HEAD & MWD COMMUNICATIONS TOH 150'
	18:00 - 23:59	5.98	DRLSUR	02	D	P		LAY DERICK OVER, CHANGE OUT POWER HEAD UNIT, TIH 150' TAG @ 2380' DRL F/2380' T/2856' (476'@ 72.9 ' PER HR) WOB 20K RPM 45 UP/DWN/ROT 83/75/78 PSI ON/OFF 1900/1650 M.W. 8.4 #
3/21/2012	0:00 - 2:00	2.00	DRLSUR	05	C	P		.41' RIGHT - 1.04' LOW OF TARGET CIRCULATE FOR CASING

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	2:00 - 6:00	4.00	DRLSUR	06	D	P		LDDS, BHA & DIRECTIONAL TOOLS
	6:00 - 6:30	0.50	DRLSUR	12	A	P		MOVE PIPE RACKS AND CATWALK. PULL DIVERTER HEAD. RIG UP TO RUN CSG. MOVE CSG INTO POSITION TO P/U.
	6:30 - 9:00	2.50	DRLSUR	12	C	P		RUN 64 JTS 8 5/8, 28# J55 CASING SET SHOE @ 2821' SET BAFFLE @ 2776.5' LAND CASING @ 09:00
	9:00 - 9:30	0.50	DRLSUR	12	B	P		HOLD SAFETY MEETING, PUMP ON CASING RUN 200' OF 1". RIG DOWN RIG MOVE OFF WELL, REBUILD DITCH. RIG UP CEMENT TRUCK, 2" HARD LINES,.
	9:30 - 12:00	2.50	DRLSUR	12	E	P		HOLD SAFETY MEETING. PRO PETRO CMTERS MAKE UP HEAD & LOAD PLUG TEST LINES TO 2000 PSI. PUMP 50 BBLs OF 8.4# H2O AHEAD, FULL RETURNS PUMP 20 BBLs OF 8.4# GEL WATER AHEAD. PUMP 220 SX (149 BBLs) 11# 3.82 YIELD LEAD CEMENT. PUMP 200 SX (41 BBLs) OF 15.8# 1.15 YIELD TAIL (2% CALC, 1/4# /SK OF FLOCELE). DROP PLUG ON FLY AND DISPLACE W/ 173.6 BBLs OF 8.4# H2O. LIFT PRESSURE 600 PSI. BUMP PLUG AND HOLD 900 PSI FOR 5 MIN. FLOAT HELD RETURNS THRU OUT JOB 40 BBLs LEAD CEMENT TO SURF PUMP 125 SX (25.6 BBLs) 15.8# CMT W/4% CALCIUM DOWN 1". CEMENT FELL BACK RELEASE RIG @ 12:00
	12:00 - 12:00	0.00	DRLSUR	13	A	P		WOC, 1.5 HOURS PUMP 85 SKS (17.4 BBLs) CMT TO SURFACE CEMENT HELD CLEAN TRUCKS & RIG DWN CMTERS
8/13/2012	8:00 - 0:00	16.00	RDMO	01	E	P		RIG DOWN ROTARY TOOL
8/14/2012	0:00 - 6:00	6.00	RDMO	01	E	P		RIG DOWN, WAIT ON DAYLIGHT
	6:00 - 18:30	12.50	MIRU	01	A	P		RIG MOVE 7 MILES TO THE NBU 921-20F (9-HAUL TRUCKS, 6- BED TRUCKS, 2-FORKLIFTS, 2-PUSHERS ON LOC @ 06:30, RELEASED @ 16:30) (J&C CRANE 1 OPERATOR & 4 OILERS, 06:30 TO 18:30) RAISED DERRICK @ 17:00, (9 EXTRA RIG HANDS)
	18:30 - 21:00	2.50	MIRU	01	B	P		RIG UP TOP DRIVE & GUIDE RAIL, SERVICE LOOP. STAND PIPE, TOTCO & BACK YARD, ELECTRICAL, PUMPS, ETC
	21:00 - 22:00	1.00	DRLPRV	14	A	P		NIPPLE UP SWACO
	22:00 - 0:00	2.00	DRLPRV	14	A	P		NIPPLE UP BOPE
8/15/2012	0:00 - 1:00	1.00	DRLPRV	14	A	P		NIPPLE UP BOPE, CHOKE LINE, GAS BUSTER, FLARE LINES
	1:00 - 5:00	4.00	DRLPRV	15	A	P		TEST BOPE, PIPE RAMS, BLIND RAMS, INNER & OUTER CHOKE VALVES, KILL LINE, 250 LOW-5000 HIGH, ANN 250 LOW-2500 HIGH
	5:00 - 6:00	1.00	DRLPRV	15	A	P		TEST MI SWACO 250 LOW 1000 HIGH
	6:00 - 8:00	2.00	DRLPRV	22	L	Z		REPAIR SWACO AIRLINES
	8:00 - 11:00	3.00	DRLPRV	22	L	Z		REPLACE SMITH ROTATING HEAD, UNABLE TO TEST
	11:00 - 12:00	1.00	DRLPRV	15	A	P		TEST MI SWACO 250 LOW- 1000 HIGH
	12:00 - 12:30	0.50	DRLPRV	14	B	P		INSTALL WEAR BUSHING

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	12:30 - 16:00	3.50	DRLPRV	06	A	P		HELD SAFETY MEETING WITH P/U, RIG & DIR CREWS, R/U & P/U BHA & SCRIBE, P/U HWDP & D/P TO TOP OF CEMENT OF 2700'
	16:00 - 16:30	0.50	DRLPRV	09	A	P		CUT & SLIP DRILL LINE
	16:30 - 19:30	3.00	DRLPRV	06	H	Z		PULL OUT OF HOLE & REPLACE MWD TOOL, (HAD GOOD ROLL TEST & TEST ON SURFACE, RUNNING IN HOLE STARTED TO LOSS SIGNAL, AFTER PICKING UP PIPE , TRIP OUT & REPLACE TOOL)
	19:30 - 21:30	2.00	DRLPRV	02	F	P		DRILL CEMENT, BAFFLE , SHOE & OPEN HOLE TO 2871, SHOE @ 2881', BAFFLE @ 2790'
	21:30 - 0:00	2.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 2871 TO 3170', 299' @ 119.6' PH WOB / 20-22 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 8.5 PPG 26 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 1800-1500, DIFF 200-500 PU/SO/RT = 100-80-90 K LOST 0 BBLS TO FORMATION SLIDE = ROT = 100% NOV/ 2- CONVENTIONAL 5' S & 2.5 E OF TARGET CENTER SWACO ON LINE @ 3100', 0 DRILL FLARE, 0 CONN FLARE ANN PSI - DRILLING 160, CONN 200
8/16/2012	0:00 - 16:00	16.00	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 3170' TO 5125', 1955' @ 122.2' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 8.8 PPG 35 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2200-1800, DIFF 200-500 PU/SO/RT = 120-100-110 K LOST 120 BBLS TO FORMATION, DUE TO SWACO SHUT IN PSI OF 1300 ON CONN SLIDE = 50' IN .67 HRS = 74.6' PH ROT = 1905' IN 15.33 HRS = 124.3' PH NOV/ 2- CONVENTIONAL 19' S & 6.7 E OF TARGET CENTER SWACO ON LINE @ 3100' 0 DRILL FLARE, 0 CONN FLARE ANN PSI - DRILLING 160, CONN 200
	16:00 - 16:30	0.50	DRLPRV	07	A	P		SERVICE RIG, BOP DRILL 68 SEC, F/T ANN & HCR VALVE

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	16:30 - 19:00	2.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 5125 TO 5343', 218' @ 87.2' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 8.8 PPG 36 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2200-1800, DIFF 200-500 PU/SO/RT = 125-100-115 K SLIDE = 32' IN .5 HRS = 64' PH ROT = 186' IN 2 HRS = 93' PH NOV/ 2- DEWATERING 19' S & 6.6 E OF TARGET CENTER SWACO ON LINE @ 3100' 0 DRILL FLARE, 0 CONN FLARE ANN PSI - DRILLING 160, CONN 200
	19:00 - 21:00	2.00	DRLPRV	08	A	P		SCHEDULED MAINTENANCE ON TOP DRIVE (TRUBLE SHOOT OIL PSI)
	21:00 - 23:30	2.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 5343 TO 5567', 224' @ 89.6' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 8.8 PPG 39 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2300-1900, DIFF 200-500 PU/SO/RT = 130-100-115 K SLIDE = 27' IN .5 HRS = 54' PH ROT = 197' IN 2 HRS = 98.5' PH NOV/ 2- CONVENTIONAL 14'S & 4.6 E OF TARGET CENTER SWACO ON LINE @ 3100' 0 DRILL FLARE, 0 CONN FLARE ANN PSI - DRILLING 160, CONN 200
	23:30 - 0:00	0.50	DRLPRV	08	B	Z		CHANGE OUT PUMP PARTS
8/17/2012	0:00 - 11:30	11.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 5567' TO 6548', 981' @ 85.3' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 8.9 PPG 39 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2400-2000, DIFF 200-500 PU/SO/RT = 160-130-145 K SLIDE = 14' IN .25 HRS = 28' PH ROT = 967' IN 11 HRS = 87.9' PH NOV/ 2- CONVENTIONAL 21N & 14W OF TARGET CENTER SWACO ON LINE @ 3100' 0 DRILL FLARE, 0 CONN FLARE ANN PSI - DRILLING 160, CONN 200 NO MUD LOSS

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	11:30 - 14:00	2.50	DRLPRV	08	B	P		SCHEDULED MAINTENANCE (TROUBLE SHOOT OIL PSI & HEAT ON TOP DRIVE WITH NOV TECH'S FROM HOUSTON) (DID NOT FIX IT), PULL 2 STANDS OFF BOTTOM, DID NOT FIND PROBLEM, OFFICE SAID RUN IT & WILL REPLACE OR FIX ON RIG MOVE
	14:00 - 17:30	3.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 6548' TO 6831', 283' @ 80.8' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 9.0 PPG 39 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2400-2000, DIFF 200-500 PU/SO/RT = 160-130-145 K SLIDE = 20' IN .42 HRS = 47.6' PH ROT = 263' IN 3.08 HRS = 85.4' PH NOV/ 2- DEWATERING, ADD GYP TO RAISE HARDNESS TO CUT BETTER 27N & 17W OF TARGET CENTER SWACO ON LINE @ 3100' 0 DRILL FLARE, 0 CONN FLARE ANN PSI - DRILLING 160, CONN 200 NO MUD LOSS
	17:30 - 18:00	0.50	DRLPRV	07	A	P		SERVICE RIG, BOP DRILL 69 SEC, F/T ANN & HCR, F/T CROWN-O-MATIC
	18:00 - 0:00	6.00	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 6831' TO 412' @ 68.6' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 9.0 PPG 35 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2400-2000, DIFF 200-500 PU/SO/RT = 170-145-160 K SLIDE = ROT = 100% NOV/ 2-DEWATERING 50' N & 20' W OF TARGET CENTER SWACO ON LINE @ 3100' 0 DRILL FLARE, 0 CONN FLARE ANN PSI - DRILLING 160, CONN 200 NO MUD LOSS

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
8/18/2012	0:00 - 13:30	13.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 7243 TO 8064', 821' @ 60.8' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 9.0 PPG 36 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2400-2000, DIFF 200-500 PU/SO/RT = 180-155-170 K SLIDE = 32' IN .83 HRS = 38.5' PH ROT = 789' IN 12.67 HRS = 62.3' PH NOV/ 2-DEWATERING, MIXING GYP FOR HARDNESS TO HELP CUT DRYER 65' N & 20' W OF TARGET CENTER SWACO ON LINE @ 3100' ANN PSI - DRILLING 180, CONN 200 0 DRILL FLARE, 0 CONN FLARE NO MUD LOSS
	13:30 - 14:00	0.50	DRLPRV	07	A	P		SERVICE RIG, CHANGE OIL IN TOP DRIVE
	14:00 - 0:00	10.00	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 8064' TO 8632', 568' @ 56.8' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 200 GPM 586 MW 9.1 PPG 36 VIS TRQ ON/OFF = 4-7 K PSI ON /OFF 2500-2100, DIFF 200-500 PU/SO/RT = 190-166-180 K SLIDE = ROT = 100% NOV/ 1-DEWATERING, 1-CONVENTIONAL 74' N & 18' W OF TARGET CENTER SWACO ON LINE @ 3100' ANN PSI - DRILLING 190, CONN 300 FLARE CAME IN @ 8500' 5 DRILL FLARE, 10 CONN FLARE 80 MUD LOSS TO SEEPAGE @ 8500'
8/19/2012	0:00 - 17:00	17.00	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 8632' TO 9677', 1045' @ 61.5' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 180 GPM 528 MW 9.1 PPG 37 VIS TRQ ON/OFF = 6-8 K PSI ON /OFF 2500-2100, DIFF 200-500 PU/SO/RT = 210-175-185 K SLIDE = 0 ROT = 100% NOV/ 1-DEWATERING, 1-CONVENTIONAL 63' N & 4' W OF TARGET CENTER SWACO ON LINE @ 3100' ANN PSI - DRILLING 230, CONN 400 FLARE CAME IN @ 9150' 10 DRILL FLARE, 20 CONN FLARE 40 BBL MUD LOSS TO SEEPAGE PUMPING 10 BBL 10% SWEEPS

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	17:00 - 17:30	0.50	DRLPRV	07	A	P		SERVICE RIG, BOP DRILL 69 SEC, F/T ANN & HCR VALVE
	17:30 - 0:00	6.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 9677 TO 9996', 319' @ 49' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 180 GPM 528 MW 9.8 PPG 40 VIS TRQ ON/OFF = 6-8 K PSI ON /OFF 2500-2100, DIFF 200-500 PU/SO/RT = 225-170-200 K SLIDE = 0 ROT = 100% NOV/ 1-DEWATERING, 1-CONVENTIONAL 55' N & 2' E W OF TARGET CENTER SWACO ON LINE @ 3100' ANN PSI - DRILLING 220, CONN 400 FLARE CAME IN @ 9150' 10 DRILL FLARE, 20 CONN FLARE 40 BBL MUD LOSS TO SEEPAGE PUMPING 10 BBL 10% SWEEPS
8/20/2012	0:00 - 14:00	14.00	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 9,996' TO 10531', 535' @ 38.2' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 180 GPM 528 MW 10.5 PPG 40 VIS TRQ ON/OFF = 6-8 K PSI ON /OFF 2500-2100, DIFF 200-500 PU/SO/PU 225-185-200 K SLIDE = 0 ROT = 100% NOV/ 1-CONVENTIONAL, 1 OUT OF SERVICE 35'N & 15' E OF TARGET CENTER SWACO ON LINE @ 3100' ANN PSI - DRILLING 220, CONN 400 FLARE CAME IN @ 9150' 10 DRILL FLARE, 20 CONN FLARE PUMPING 10 BBL 10% SWEEPS
	14:00 - 14:30	0.50	DRLPRV	07	A	P		SERVICE RIG

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	14:30 - 0:00	9.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 10531' TO 10840', 309' @ 32.5' PH WOB / 22-24 RPM TOP DRIVE 50-60 SPM 170 GPM 498 MW 11 PPG 40 VIS TRQ ON/OFF = 6-8 K PSI ON /OFF 2500-2100, DIFF 200-500 PU/SO/PU 225-185-200 K SLIDE = 0 ROT = 100% NOV/ 1-CONVENTIONAL, 1 OUT OF SERVICE 39' N & 18' E OF TARGET CENTER SWACO ON LINE @ 3100' ANN PSI - DRILLING 220, CONN 400 FLARE CAME IN @ 9150' 10 DRILL FLARE, 20 CONN FLARE PUMPING 10 BBL 10% SWEEPS
8/21/2012	0:00 - 17:30	17.50	DRLPRV	02	B	P		CLOSED LOOP SYSTEM DRILL F/ 10840' TO 11,292', 452' @ 25.8' PH TD WELL @ 17:30 WOB / 24-26 RPM TOP DRIVE 50-60 SPM 160 GPM 440 MW 12.1 PPG 41 VIS TRQ ON/OFF = 7-8 K PSI ON /OFF 2700-2400, DIFF 200-500 PU/SO/PU 225-185-200 K SLIDE = 0 ROT = 100% NOV/ 2- BYPASS, REPLACE 1 CENTRIFUGE 24.35 N & 27.95 E OF TARGET CENTER SWACO ON LINE @ 3100', OFF LINE @ 11,170' ANN PSI - DRILLING 160, CONN 200 0 DRILL FLARE, 0 CONN FLARE PUMPING 10 BBL 10% SWEEPS SERVICE RIG, TAKE TD SURVEY
	17:30 - 18:00	0.50	DRLPRV	07	A	P		
	18:00 - 20:30	2.50	DRLPRV	05	F	P		CIRC & COND MUD, RAISE MW TO 12.3, BRING LCM TO 5% DO TO LOSS @ 12.3 MW, LOST 40 BBLs SHORT TRIP TO SHOE
	20:30 - 0:00	3.50	DRLPRV	06	E	P		
8/22/2012	0:00 - 2:30	2.50	DRLPRV	08	B	P		SCHEDULED MAINTENANCE, WORK ON TOP DRIVE OILERS, FOUND BEARING GOING OUT, NEW TOP DRIVE REPLACEMENT ON IT'S WAY FROM HOUSTON, WILL INSTALL ON RIG MOVE
	2:30 - 6:30	4.00	DRLPRV	06	E	P		TRIP IN HOLE, WASH TIGHT SPOT @ 10,300' TO 10,600 (RIGHT WEAR GAS KICK CAME FROM) TRIP IN HOLE TO TD OF 11,292', NO LOSS ON TRIP RAISE MW TO 12.5, LCM TO 10%
	6:30 - 9:00	2.50	DRLPRV	05	B	P		2nd WIPER TRIP TO SHOE & BACK, CLEAN, NO LOSS
	9:00 - 15:30	6.50	DRLPRV	06	E	P		SERVICE RIG
	15:30 - 16:00	0.50	DRLPRV	07	A	P		CIRC & COND HOLE, MAINTAIN 12.5 MW & 10% LCM
	16:00 - 19:00	3.00	DRLPRV	05	C	P		
	19:00 - 0:00	5.00	DRLPRV	06	B	P		HELD SAFETY MEETING WITH RIG & KIMZEY CREWS, RIG UP & LAYDOWN DRILL STRING LAYDOWN DRILL STRING, BHA & DIR TOOLS
8/23/2012	0:00 - 3:00	3.00	DRLPRV	06	B	P		

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: PROPETRO 11/11, PIONEER 54/54

Event: DRILLING

Start Date: 3/4/2012

End Date: 8/24/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	3:00 - 8:30	5.50	DRLPRV	11	C	P		HELD SAFETY MEETING, RIG UP & RUN OPEN HOLE LOGS TO 8184' BRIDGED OUT, LOG OUT, RIG DOWN
	8:30 - 9:00	0.50	DRLPRV	14	B	P		PULL WEAR BUSHING
	9:00 - 18:00	9.00	DRLPRV	12	C	P		HELD SAFETY MEETING WITH RIG & CASING CREWS, RIG UP & RUN 140 JTS P-110 LTC, 1 X/O & 112 DQX P-110 4.5" PROD CASING, SHOE @ 11,277', FLOAT @ 11,231', B/H MARKER @ 10,698', MESA MARKER @ 7983', X/O @ 5036', LAND CASING, RIG DOWN CASING CREW
	18:00 - 19:30	1.50	DRLPRV	05	D	P		CIRC HOLE CLEAN TO CEMENT
	19:30 - 0:00	4.50	DRLPRV	12	E	P		HELD SAFETY MEETING WITH RIG & CEMENTING CREWS, RIG UP & PSI TEST LINES TO 5000, DROP BOTTOM PLUG, PUMP 25 BBL WATER SPACER, LEAD 690 SACKS, 1.77 YLD 13 PPG, TAIL 14.3 PPG, 1.32 YLD WITH .5% EC-1, DROP PLUG & DISPLACE WITH 174.5 BBLS CLAYTREAT WATER, LOST RETURNS 80 BBLS INTO DISPLACEMENT, BUMP PLUG @ 4149 PSI (686 PSI OVER FINAL LIFT OF 3463), FLUSH STACK, CLEAN LINES & RIG DOWN
8/24/2012	0:00 - 1:00	1.00	DRLPRV	14	B	P		SET PACKOFF WITH 110 K ON HANGER
	1:00 - 3:00	2.00	DRLPRV	14	A	P		N/D SWACO
	3:00 - 6:00	3.00	DRLPRV	14	A	P		N/D BOPE, CLEAN PITS & RELEASE RIG TO THE NBU 921-8D @ 06:00 8/24/12

1 General

1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well/Wellbore Information

Well	NBU 921-20F	Wellbore No.	OH
Well Name	NBU 921-20F	Wellbore Name	NBU 921-20F
Report No.	1	Report Date	9/24/2012
Project	UTAH-UINTAH	Site	NBU 921-20F
Rig Name/No.		Event	COMPLETION
Start Date	10/9/2012	End Date	10/16/2012
Spud Date	3/19/2012	Active Datum	RKB @4,811.00usft (above Mean Sea Level)
UWI	SE/NW/0/9/S/21/E/20/0/0/26/PM/N2124/E/0/2189/0/0		

1.3 General

Contractor		Job Method		Supervisor	
Perforated Assembly		Conveyed Method			

1.4 Initial Conditions

Fluid Type		Fluid Density	
Surface Press		Estimate Res Press	
TVD Fluid Top		Fluid Head	
Hydrostatic Press		Press Difference	
Balance Cond	NEUTRAL		

1.5 Summary

Gross Interval	8,028.0 (usft)-11,061.0 (usft)	Start Date/Time	10/9/2012 12:00AM
No. of Intervals	58	End Date/Time	10/9/2012 12:00AM
Total Shots	201	Net Perforation Interval	67.00 (usft)
Avg Shot Density	3.00 (shot/ft)	Final Surface Pressure	
		Final Press Date	

2 Intervals

2.1 Perforated Interval

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
10/9/2012 12:00AM	MESAVERDE/			8,028.0	8,030.0	3.00		0.360	EXP/	3.375	120.00			23.00 PRODUCTION	N

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
10/9/2012 12:00AM	MESAVERDE/			8,044.0	8,046.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,146.0	8,149.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,252.0	8,253.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,267.0	8,268.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,293.0	8,294.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,402.0	8,403.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,415.0	8,416.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,488.0	8,489.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,516.0	8,517.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,588.0	8,589.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,623.0	8,624.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,659.0	8,661.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,723.0	8,724.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,750.0	8,752.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			8,791.0	8,792.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,009.0	9,010.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,027.0	9,028.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,049.0	9,050.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,087.0	9,088.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,174.0	9,175.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,215.0	9,216.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
10/9/2012 12:00AM	MESAVERDE/			9,231.0	9,232.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,309.0	9,310.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,342.0	9,343.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,370.0	9,371.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,394.0	9,395.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,420.0	9,421.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,441.0	9,442.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,476.0	9,477.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,494.0	9,495.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,562.0	9,563.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,613.0	9,614.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,638.0	9,639.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,670.0	9,671.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,695.0	9,696.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,744.0	9,745.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,761.0	9,762.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,771.0	9,772.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,824.0	9,825.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,840.0	9,841.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,881.0	9,882.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			9,963.0	9,964.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

2.1 Perforated Interval (Continued)

Date	Formation/ Reservoir	CCL@ (usft)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Density (shot/ft)	Misfires/ Add. Shot	Diamete r (in)	Carr Type /Stage No	Carr Size (in)	Phasing (°)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	Misrun
10/9/2012 12:00AM	MESAVERDE/			10,004.0	10,005.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,075.0	10,077.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,768.0	10,770.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,796.0	10,797.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,823.0	10,824.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,834.0	10,836.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,848.0	10,849.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,859.0	10,860.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,914.0	10,915.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,937.0	10,938.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,944.0	10,945.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,946.0	10,947.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			10,974.0	10,974.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			11,032.0	11,033.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			11,051.0	11,052.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	
10/9/2012 12:00AM	MESAVERDE/			11,060.0	11,061.0	3.00		0.360	EXP/	3.375	120.00		23.00	PRODUCTIO N	

3 Plots

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F			Spud Date: 3/19/2012		
Project: UTAH-UINTAH		Site: NBU 921-20F		Rig Name No: SWABBCO 6/6, SWABBCO 6/6	
Event: COMPLETION		Start Date: 10/9/2012		End Date: 10/16/2012	
Active Datum: RKB @4,811.00usft (above Mean Sea Level)			UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
9/24/2012	8:00 - 8:15	0.25	FRAC	48		P		HELD SAFETY MEETING , HIGH PRESSURE
	8:15 - 11:30	3.25	FRAC	33	C	P		FILL SURFACE CSG. MIRU B&C QUICK TEST. FILL 4 1/2 WITH 17 BBLS TMAC PSI TEST T/ 1000 PSI. HELD FOR 15 MIN LOST 11 PSI. PSI TEST T/ 3500 PSI. HELD FOR 15 MIN LOST 55 PSI. 1ST PSI TEST T/ 9000 PSI. HELD FOR 30 MIN LOST 87 PSI. NO COMMUNICATION OR MIGRATION WITH SURFACE CSG BLEED OFF PSI.SWMFN RU HOT OILER FILLED SURFACE WITH TMAC, PRESSURED TO 750 PSI ESTABLISHED INJECTION RATE DOWN SURFACE @ 2 BPM, 600 PSI, PUMPED 10 BBLS, ISIP 500 PSI SWI
9/26/2012	7:00 - 7:15	0.25	FRAC	48		P		HELD SAFETY MEETING: FACE MASKS FOR CEMENT
	7:15 - 10:00	2.75	FRAC	51	B	P		RU SCHLUMBERGER, TEST PUMP & LINES ESTABLISH INJECTION RATE 3 BPM 450 PSI, PREFORMED TOP JOB AS FOLLOWS PUMPED 10 BBLS FRESH WATER PUMPED 10 BBLS S001 WATER PUMPED 10 BBLS FRESH WATER PUMPED 10 BBLS ZONE LOCK PUMPED 10 BBLS FRESH WATER PUMPED 440 SKS THIXOTROPIC CLASS G CEMENT 151 BBLS, CEMENT @ 12.5 PPG CEMENT PUMPED 3 BBL DISPLACEMENT AVERAGE PRESSURE 563 PSI AVERAGE RATE 2.9 BPM, ISIP 450 PSI SHUT WELL IN WITH 350 PSI. TOTAL FLUID PUMPED 204 BBLS
9/27/2012	-							
9/28/2012	-							
9/29/2012	-							
10/9/2012	7:00 - 7:15	0.25	FRAC	48		P		JSA= MOVING EQUIP
	7:15 - 18:00	10.75	FRAC	30		P		RD RIG ON NBU 1022-4M MOVE RIG & EQUIP TO LOC RU RIG ND W/H NU BOPS RU FLOOR & TUBING EQUIP TALLY & PU TUBING 250 JNTS EOT @ 7904' POOH SIW SDFN JSA= W/L SAFETY
10/10/2012	7:00 - 7:15	0.25	FRAC	48		P		

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F				Spud Date: 3/19/2012				
Project: UTAH-UINTAH			Site: NBU 921-20F			Rig Name No: SWABBCO 6/6, SWABBCO 6/6		
Event: COMPLETION			Start Date: 10/9/2012				End Date: 10/16/2012	
Active Datum: RKB @4,811.00usft (above Mean Sea Level)			UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 7:15	0.00	FRAC	30		P		ND BOPS NU FRAC VALVES PLACE HNCR IN TUB HEAD TEST TO 9000 PSI RD TESTER RU W/L RIH PERF 1ST STAGE STAGE #1] PU RIH W/ 3-3/8" GUN, 23 GM, .36 HOLE LMV 11060-61' 3 SPF 3 HOLES LMV 11051-52' 3 SPF 3 HOLES LMV 11032-33' 3 SPF 3 HOLES LMV 10974-75' 3 SPF 3 HOLES LMV 10944-45 3 SPF 3 HOLES LMV 10937-38 3 SPF 3 HOLES LMV 10914-15 3 SPF 3 HOLES SVM SDFN SUPERIOR TO RU THIS AFTERNOON TO BE READY TO FRAC FIRST THING IN MORNING JSA= FRAC
10/11/2012	7:00 - 7:15	0.25	FRAC	48		P		

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F		Spud Date: 3/19/2012	
Project: UTAH-UINTAH	Site: NBU 921-20F		Rig Name No: SWABBCO 6/6, SWABBCO 6/6
Event: COMPLETION	Start Date: 10/9/2012		End Date: 10/16/2012
Active Datum: RKB @4,811.00usft (above Mean Sea Level)		UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 18:00	10.75	FRAC	30		P		<p>MIRU SUPERIOR PRESS TEST PUMPS & LINES 9500 PSI CHECK & SET POP OFF ON SURFACE 8800 PSI</p> <p>STAGE #1] WELLHEAD PRESS=1750 psi BREAK PRESS=4904 PSI INJ RT=51.9 INJ PSI=6299# FG=.76 W/ 21/21.PERFS OPEN, MAX PSI=7828# MAX RT= 52.3 AP= 6462# AR=49.8 FG=.78 ISIP=3798# NPI=251# PUMPED 3461 BBLS SLICK WTR , W/ 81758 # 30/50 TLC SAND</p> <p>STAGE#2] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @10890' , PERF LMV @ , W/ 23 GM, .36" HOLES, 24 HOLES AS PER PROC. LMV, 10859-60' 3 SPF 3 HOLES LMV, 10848-49' 3 SPF 3 HOLES LMV, 10834-36' 3 SPF 6 HOLES LMV, 10823-24' 3 SPF 3 HOLES LMV, 10796-97' 3 SPF 3 HOLES LMV, 10768-70 3 SPF 6 HOLES 24 HOLES</p> <p>WELLHEAD PRESS=2440 PSI BREAK PRESS=5138 PSI, INJ RT= 48.8, INJ PSI=6345 PSI, FG=.79, W/ 24/24 PERF OPEN MAX PSI=7369 PSI MAX RT= 49.0, AP=6583 PSI, AR=46.8, FG=.80, ISIP=3921 PSI, NPI=98 PSI, PUMPED= 3307 BBLS SLICK WTR , W/ 81902 # 30/50 TLC SAND</p> <p>STAGE#3] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @10107' , PERF LMV @ , W/ 23 GM, .36" HOLES, 21 HOLES AS PER PROC. MESA VERDE, 10075-77' 3 SPF 6 HOLES 10004-05' 3 SPF 3 HOLES 9963-64' 3 SPF 3 HOLES 9881-82' 3 SPF 3 HOLES 9840-41' 3 SPF 3 HOLES 9824-25' 3 SPF 3 HOLES</p> <p>WELLHEAD PRESS=1173 PSI, BREAK PRESS=4192 PSI, INJ RT=45.1, INJ PSI=6345 PSI, FG=.79, W/ 14/21 PERFS OPEN, MAX PSI=8205 PSI, MAX RT=49 AP=6422 PSI, AR= 45.8, FG=.73 , W/14/21 PERFS OPEN, ISIP=2941 PSI, NPI=212 PSI, PUMPED875 BBLS SLICK WTR , W/16101 # 30/50 TLC SAND</p> <p>STAGE#4] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @9802' , PERF LMV @ , W/ 23 GM, .36" HOLES, 24 HOLES AS PER PROC. MESA VERDE, 9771-72' 3 SPF, 3 HOLES 9761-62' 3 SPF, 3 HOLES 9744-45' 3 SPF, 3 HOLES 9695-96' 3 SPF, 3 HOLES 9670-71' 3 SPF, 3 HOLES 9638-39' 3 SPF, 3 HOLES 9613-14' 3 SPF, 3 HOLES 9562-63' 3 SPF, 3 HOLES</p>

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F		Spud Date: 3/19/2012	
Project: UTAH-UINTAH	Site: NBU 921-20F	Rig Name No: SWABBCO 6/6, SWABBCO 6/6	
Event: COMPLETION	Start Date: 10/9/2012	End Date: 10/16/2012	
Active Datum: RKB @4,811.00usft (above Mean Sea Level)		UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
<p>WELLHEAD PRESS=1035 PSI, BREAK PRESS=4134 PSI, INJ RT=48.5, INJ PSI=7505 PSI, FG=.73, MAX PSI= 8221 PSI, MAX RT=49.9, AP= 6904 PSI, AR=46.0, FG=.81 , W/ 15/24 PERFS OPEN, ISIP=3596 PSI, NPI=755. PUMPED 1062 BBLS SLICK WTR , W/ 23280 # 30/50 TLC SAND</p> <p>STAGE#5] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @9528' , PERF LMV @ , W/ 23 GM, .36" HOLES, 24 HOLES AS PER PROC.</p> <p>MESA VERDE, 9494-95' 3 SPF, 3 HOLES 9476-77' 3 SPF, 3 HOLES 9441-42' 3 SPF, 3 HOLES 9420-21' 3 SPF, 3 HOLES 9394-95' 3 SPF, 3 HOLES 9370-71' 3 SPF, 3 HOLES 9342-43' 3 SPF, 3 HOLES 9309-10' 3 SPF, 3 HOLES</p> <p>SIW SDFN JSA= FRAC & W/L SAFETY</p>								
10/12/2012	7:00 - 7:15	0.25	FRAC	48		P		

US ROCKIES REGION

Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 10/9/2012

End Date: 10/16/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 15:00	7.75						<p>STAGE #5] SET CBP & PERF LAST NIGHT</p> <p>WELLHEAD PRESS=2392 PSI, BREAK PRESS=3716 PSI, INJ RT= 48.5, INJ PSI=5324 PSI, FG=.74, MAX PSI=7495 PSI, MAX RT=52.3, AP= 5482 PSI, AR=50.9, FG=.76 , W/24/24 PERFS OPEN, ISIP=3046 PSI, NPI=219 PSI, PUMPED 1082 BBLS SLICK WTR , W/24419 # 30/50 TLC SAND</p> <p>STAGE#6] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @9262' , PERF MESA VERDE , W/ 23 GM, .36" HOLES, 21 HOLES AS PER PROC.</p> <p>MESA VERDE, 9231-32' 3 SPF, 3 HOLES</p> <p>9215-16' 3 SPF, 3 HOLES</p> <p>9174-75' 3 SPF, 3 HOLES</p> <p>9087-88' 3 SPF, 3 HOLES</p> <p>9049-50' 3 SPF, 3 HOLES</p> <p>9027-28' 3 SPF, 3 HOLES</p> <p>9009-10' 3 SPF, 3 HOLES, 21 HOLES</p> <p>WELLHEAD PRESS=1903 PSI, BREAK PRESS=3714 PSI, INJ RT=49.5, INJ PSI=7954 PSI, FG=.75, MAX PSI=7588 PSI, MAX RT=51.9, AP= 6117 PSI, AR=50.4, FG=.77, , W/13/21 PERFS OPEN, ISIP=3028 PSI, NPI=154 PSI, PUMPED 1060 BBLS SLICK WTR , W/ 22250 # 30/50 TLC SAND</p> <p>STAGE#7] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @8822 , PERF MESA VERDE @ , W/ 23 GM, .36" HOLES, 24 HOLES AS PER PROC.</p> <p>MESA VERDE, 8791-92, 3 SPF, 3 HOLES</p> <p>8750-52', 3 SPF, 6 HOLES</p> <p>8723-24', 3 SPF, 3 HOLES</p> <p>8659-61, 3 SPF, 6 HOLES</p> <p>8623-24', 3 SPF, 3 HOLES</p> <p>8588-89', 3 SPF, 3 HOLES</p> <p>WELLHEAD PRESS=1367 PSI, BREAK PRESS=3623' PSI, INJ RT=52, INJ PSI= 5736 PSI, FG= .75, MAX PSI=6400 MAX RT=52.3, AP=5120 PSI, AR= 51.2, FG=.78, , W/ 22/24 PERFS OPEN, ISIP=2970 PSI, NPI=244 PSI, PUMPED 1020 BBLS SLICK WTR , W/ 23170 # 30/50 TLC SAND</p> <p>STAGE#8] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @8547' , PERF LMV @ , W/ 23 GM, .36" HOLES, 21 HOLES AS PER PROC.</p> <p>MESA VERDE, 8516-17' 3 SPF, 3 HOLES</p> <p>8488-89' 3 SPF, 3 HOLES</p> <p>8415-16' 3 SPF, 3 HOLES</p> <p>8402-03', 3 SPF, 3 HOLES</p> <p>8293-94', 3 SPF, 3 HOLES</p> <p>8267-68', 3 SPF, 3 HOLES</p> <p>8252-53', 3 SPF, 3 HOLES 21 HOLES</p> <p>WELLHEAD PRESS=2112 PSI, BREAK PRESS=3164 PSI, INJ RT=52.4, INJ PSI=2527 PSI, FG=.74, MAX PSI=5414 PSI, MAX RT= 52.8, AP=5090 PSI,</p>

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 10/9/2012

End Date: 10/16/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
								AR= 51.7, FG=.78, , W/ 21/21 PERFS OPEN, ISIP=2844 PSI, NPI= 317 PSI, PUMPED 949 BBLS SLICK WTR , W/ 22215 # 30/50 TLC SAND
								STAGE#9] PU RIH W/ CBP & 3-3/8" PERF GUN SET CBP @8179' , PERF MESA VERDE @ , W/ 23 GM, .36" HOLES, 21 HOLES AS PER PROC. MESA VERDE, 8146-49', 3 SPF, 9 HOLES 8044-46' 3 SPF, 6 HOLES 8028-30' 3 SPF, 6 HOLES 21 HOLES
								WELLHEAD PRESS=1098 PSI, BREAK PRESS= 2590 PSI, INJ RT=52.1, INJ PSI=5461 PSI, FG=.67, MAX PSI=6364 PSI, MAX RT=52.8, AP= 4879 PSI, AR=51.7, FG= .76 , W/ 18/21 PERFS OPEN, ISIP=2626 PSI, NPI=758 PSI, PUMPED 493 BBLS SLICK WTR , W/ 23385 # 30/50 TLC SAND
								PU KILL PLUG PULL INTO LUBE PULL OUT OF ROPE SOCKET DROP PLUG ONTO VALVE LAY DOWN W/L REHEAD PU W/L EQUIP RIH TAG ON PIECE OF PLUG POOH PU GUAGE RNG RIH TO 8010' POOH W/ JUNK BASKET PU CBP RIH SET @ 7978' SIW RD W/L & FRAC EQUIP SIW SDFW PUMPED 13309 TOTAL CLEAN BBLS PUMPED 318480# SAND JSA= DRILL CBPS
10/15/2012	7:00 - 7:15	0.25	DRLOUT	48		P		

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 10/9/2012

End Date: 10/16/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW/0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 17:00	9.75	DRLOUT	30		P		<p>SIWP= 0 PSI ND FRAC VALES NU 10K BOPS RU FLOOR & TUBING EQUIP PU POBS PKG RIH TAG 1 ST PLUG @ 7918' RU DRLG EQUIP EST CIRC TEST BOPS TO 3000 PSI .</p> <p>PLUG #1] DRILL THRU HALLI 8K CBP @ 7978' IN 7 MIN W/ 100 PSI INCREASE</p> <p>PLUG #2] CONTINUE TO RIH TAG SAND @ 8159' (20' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8179' IN 7 MIN W/ 100 PSI INCREASE</p> <p>PLUG #3] CONTINUE TO RIH TAG SAND @ 8527' (25' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8547' IN 9 MIN W/ 150# INCREASE</p> <p>PLUG #4] CONTINUE TO RIH TAG SAND @ 8797' (20' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8822' IN 8 MIN W/ 100 PSI INCREASE</p> <p>PLUG #5] CONTINUE TO RIH TAG SAND @ 9232' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @ 9262' IN 11 MIN W/ 150# INCREASE</p> <p>PLUG #6] CONTINUE TO RIH TAG SAND @ 9498' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @ 9528' IN 10 MIN W/ 150# INCREASE</p> <p>PLUG #7] CONTINUE TO RIH TAG SAND @ 9772' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @ 9802' IN 9 MIN W/ 100# INCREASE CONTINUE TO RIH 2 JNTS ALLOW WELL TO FLOW 45 MIN TO CLEAN UP SIW SDFN</p>
10/16/2012	7:00 - 7:15	0.25	DRLOUT	48		P		JSA= LANDING TUBING

US ROCKIES REGION
Operation Summary Report

Well: NBU 921-20F

Spud Date: 3/19/2012

Project: UTAH-UINTAH

Site: NBU 921-20F

Rig Name No: SWABBCO 6/6, SWABBCO 6/6

Event: COMPLETION

Start Date: 10/9/2012




End Date: 10/16/2012

Active Datum: RKB @4,811.00usft (above Mean Sea Level)

UWI: SE/NW0/9/S/21/E/20/0/0/26/PM/N/2124/E/0/2189/0/0

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	7:15 - 15:00	7.75	DRLOUT	30		P		SIWP= 2900 PSI OPEN WELL TO PIT RIH TAG FILL
								PLUG #8] CONTINUE TO RIH TAG SAND @ 10087' (20' FILL) C/O & DRILL THRU HALLI 8K CBP @ 10107' IN 11 MIN W/ 250# INCREASE
								PLUG #9] CONTINUE TO RIH TAG SAND @ 10865' (25' FILL) C/O & DRILL THRU HALLI 8K CBP @ 10890' IN 11 MIN W/ 700# INCREASE
								PBTD] CONTINUE TO RIH TAG SAND @ 11060' (190' FILL) C/O & DRILL TO 11130' COULDNT MAKE HOLE TUB JUST SPINS POOH LD 13 JNTS LAND TUBING ON HNGR W/ 339 JNTS 2-3/8" P-110 EOT @ 10742.44' ND BOPS NU WELLHEAD
								TUBING DETAIL K.B.....19.00' HANGER.....83" 339 JNTS 2-3/8" P-110.....10720.41' POBS.....2.20 EOT@.....10742.44'
								TOTAL FLUID PUMPED= 13309 BBLS RIG REC= 3000 BBLS LEFT TO REC= 10309 BBLS
								TUB DEL= 377 JNTS USED= 339 JNTS RETURNED= 38 JNTS
	15:00 - 15:00	0.00	DRLOUT	50				WELL TURNED TO SALES @ 1115 HR ON 10/16/2012 1100 MCFD, 1920 BWPD, FCP 2750#, FTP 1900#, 20/64" CK.
10/20/2012	7:00 -			50				WELL IP'D ON 10/20/12 - 3234 MCFD, 624 BWPD, 0 BOPD, CP 2#, FTP 2392#, LP 254#, 24 HRS, CK 20/64

WELL DETAILS: NBU 921-20F					
GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)					
+W-S	+E-W	Northing	Easting	Latitude	Longitude
0.00	0.00	14537619.81	2038948.88	40.023044	-109.576514



PROJECT DETAILS: UTAH - UTM (feet), NAD27, Zone 12N
 Geodetic System: Universal Transverse Mercator (US Survey Feet)
 Datum: NAD 1927 (NADCON CONUS)
 Ellipsoid: Clarke 1886
 Zone: Zone 12N (114 W to 108 W)
 Location: SECTION 20 T9S R21E
 System Datum: Mean Sea Level

Design: OH (NBU 921-20F/OH)

Created By: Gabe Kendall Date: 14:06, August 28 2012



US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

NBU 921-20F

NBU 921-20F

OH

Design: OH

Standard Survey Report

28 August, 2012



Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 921-20F
Well: NBU 921-20F
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well NBU 921-20F
TVD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
MD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Project UTAH - UTM (feet), NAD27, Zone 12N
Map System: Universal Transverse Mercator (US Survey Feet) **System Datum:** Mean Sea Level
Geo Datum: NAD 1927 (NADCON CONUS)
Map Zone: Zone 12N (114 W to 108 W)

Site NBU 921-20F, SECTION 20 T9S R21E
Site Position: **Northing:** 14,537,619.61 usft **Latitude:** 40.023044
From: Lat/Long **Easting:** 2,038,948.88 usft **Longitude:** -109.576514
Position Uncertainty: 0.00 ft **Slot Radius:** 13.200 in **Grid Convergence:** 0.92 °

Well NBU 921-20F, 2125 FNL 2189 FWL
Well Position **+N/-S** 0.00 ft **Northing:** 14,537,619.61 usft **Latitude:** 40.023044
+E/-W 0.00 ft **Easting:** 2,038,948.88 usft **Longitude:** -109.576514
Position Uncertainty 0.00 ft **Wellhead Elevation:** ft **Ground Level:** 4,792.00 ft

Wellbore OH
Magnetics **Model Name** **Sample Date** **Declination (°)** **Dip Angle (°)** **Field Strength (nT)**
 IGRF2010 03/12/12 11.02 65.85 52,259

Design OH
Audit Notes:
Version: 1.0 **Phase:** ACTUAL **Tie On Depth:** 0.00
Vertical Section: **Depth From (TVD) (ft)** **+N/-S (ft)** **+E/-W (ft)** **Direction (°)**
 0.00 0.00 0.00 322.24

Survey Program **Date** 08/28/12

From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description
15.00	2,808.00	Survey #1 SDI MWD SURFACE (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1
2,890.00	11,292.00	Survey #2 SDI MWD PRODUCTION (OH)	SDI MWD	SDI MWD - Standard ver 1.0.1

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
15.00	0.00	0.00	15.00	0.00	0.00	0.00	0.00	0.00	0.00
184.00	0.53	93.54	184.00	-0.05	0.78	-0.52	0.31	0.31	0.00
FIRST SDI MWD SURFACE SURVEY									
266.00	0.44	102.60	265.99	-0.14	1.47	-1.01	0.14	-0.11	11.05
355.00	0.53	84.14	354.99	-0.17	2.21	-1.49	0.20	0.10	-20.74
445.00	0.43	293.08	444.99	0.00	2.31	-1.41	1.03	-0.11	-167.84
535.00	0.62	279.26	534.99	0.21	1.52	-0.76	0.25	0.21	-15.36
625.00	0.70	281.36	624.98	0.40	0.50	0.01	0.09	0.09	2.33
715.00	0.79	293.23	714.97	0.75	-0.61	0.97	0.20	0.10	13.19

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 921-20F
Well: NBU 921-20F
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well NBU 921-20F
TVD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
MD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
805.00	0.35	321.27	804.97	1.21	-1.35	1.78	0.56	-0.49	31.16
895.00	0.35	25.51	894.97	1.67	-1.40	2.18	0.41	0.00	71.38
985.00	0.44	38.43	984.96	2.19	-1.07	2.39	0.14	0.10	14.36
1,075.00	0.18	14.70	1,074.96	2.60	-0.82	2.56	0.32	-0.29	-26.37
1,165.00	0.18	134.66	1,164.96	2.64	-0.68	2.50	0.35	0.00	133.29
1,255.00	0.35	182.84	1,254.96	2.26	-0.60	2.15	0.30	0.19	53.53
1,345.00	0.53	169.57	1,344.96	1.58	-0.53	1.58	0.23	0.20	-14.74
1,435.00	0.44	147.77	1,434.96	0.88	-0.27	0.86	0.23	-0.10	-24.22
1,525.00	0.70	134.06	1,524.95	0.20	0.30	-0.03	0.32	0.29	-15.23
1,615.00	0.70	160.16	1,614.95	-0.70	0.89	-1.09	0.35	0.00	29.00
1,705.00	0.26	148.74	1,704.94	-1.39	1.18	-1.82	0.50	-0.49	-12.69
1,795.00	0.18	322.59	1,794.94	-1.45	1.20	-1.88	0.49	-0.09	193.17
1,885.00	0.35	288.57	1,884.94	-1.25	0.85	-1.51	0.25	0.19	-37.80
1,975.00	0.35	255.96	1,974.94	-1.23	0.33	-1.17	0.22	0.00	-36.23
2,065.00	0.44	255.44	2,064.94	-1.38	-0.28	-0.92	0.10	0.10	-0.58
2,245.00	0.26	188.29	2,244.93	-1.96	-1.00	-0.94	0.23	-0.10	-37.31
2,335.00	0.35	160.69	2,334.93	-2.42	-0.94	-1.34	0.19	0.10	-30.67
2,425.00	0.35	156.30	2,424.93	-2.93	-0.74	-1.87	0.03	0.00	-4.88
2,515.00	0.44	51.53	2,514.93	-2.97	-0.36	-2.13	0.70	0.10	-116.41
2,605.00	0.44	53.99	2,604.93	-2.55	0.19	-2.13	0.02	0.00	2.73
2,695.00	0.57	0.66	2,694.92	-1.90	0.47	-1.79	0.52	0.14	-59.26
2,785.00	0.35	325.05	2,784.92	-1.23	0.32	-1.17	0.39	-0.24	-39.57
2,808.00	0.44	6.18	2,807.92	-1.08	0.29	-1.03	1.26	0.39	178.83
LAST SDI MWD SURFACE SURVEY									
2,890.00	0.18	348.46	2,889.92	-0.64	0.30	-0.69	0.33	-0.32	-21.61
FIRST SDI MWD PRODUCTION SURVEY									
2,984.00	0.00	223.66	2,983.92	-0.50	0.27	-0.56	0.19	-0.19	0.00
3,080.00	0.26	193.77	3,079.92	-0.71	0.22	-0.70	0.27	0.27	0.00
3,175.00	0.79	149.12	3,174.92	-1.48	0.50	-1.48	0.67	0.56	-47.00
3,270.00	0.97	160.02	3,269.90	-2.80	1.11	-2.90	0.26	0.19	11.47
3,364.00	1.14	156.86	3,363.89	-4.41	1.75	-4.56	0.19	0.18	-3.36
3,459.00	0.26	332.90	3,458.88	-5.08	2.03	-5.26	1.47	-0.93	185.31
3,554.00	0.26	96.30	3,553.88	-4.92	2.14	-5.20	0.48	0.00	129.89
3,649.00	0.18	124.69	3,648.88	-5.02	2.48	-5.49	0.14	-0.08	29.88
3,744.00	0.62	152.29	3,743.88	-5.56	2.84	-6.14	0.49	0.46	29.05
3,839.00	0.70	166.70	3,838.87	-6.58	3.21	-7.17	0.19	0.08	15.17
3,934.00	0.79	166.09	3,933.87	-7.78	3.50	-8.30	0.10	0.09	-0.64
4,028.00	1.14	151.32	4,027.85	-9.23	4.11	-9.82	0.45	0.37	-15.71
4,123.00	0.21	260.53	4,122.85	-10.09	4.39	-10.67	1.29	-0.98	114.96
4,218.00	0.53	153.34	4,217.84	-10.51	4.42	-11.02	0.66	0.34	-112.83
4,312.00	0.88	180.15	4,311.84	-11.62	4.61	-12.01	0.50	0.37	28.52
4,407.00	0.67	184.96	4,406.83	-12.91	4.56	-13.00	0.23	-0.22	5.06
4,501.00	0.66	180.86	4,500.82	-14.00	4.50	-13.82	0.05	-0.01	-4.36

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 921-20F
Well: NBU 921-20F
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well NBU 921-20F
TVD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
MD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,596.00	0.87	162.30	4,595.81	-15.23	4.72	-14.93	0.34	0.22	-19.54
4,691.00	1.08	167.07	4,690.80	-16.79	5.14	-16.42	0.24	0.22	5.02
4,785.00	0.12	186.20	4,784.79	-17.75	5.32	-17.29	1.03	-1.02	20.35
4,880.00	0.26	101.84	4,879.79	-17.89	5.52	-17.53	0.29	0.15	-88.80
4,974.00	0.53	137.61	4,973.79	-18.26	6.02	-18.12	0.38	0.29	38.05
5,069.00	0.79	142.71	5,068.79	-19.10	6.72	-19.22	0.28	0.27	5.37
5,164.00	1.41	154.71	5,163.77	-20.68	7.61	-21.01	0.69	0.65	12.63
5,258.00	0.88	317.08	5,257.76	-21.20	7.62	-21.42	2.41	-0.56	172.73
5,353.00	1.58	340.11	5,352.74	-19.43	6.67	-19.45	0.89	0.74	24.24
5,448.00	1.23	338.53	5,447.71	-17.25	5.86	-17.23	0.37	-0.37	-1.66
5,542.00	2.64	337.03	5,541.65	-14.32	4.64	-14.16	1.50	1.50	-1.60
5,637.00	2.55	334.49	5,636.56	-10.40	2.88	-9.98	0.15	-0.09	-2.67
5,732.00	2.37	334.40	5,731.47	-6.72	1.12	-6.00	0.19	-0.19	-0.09
5,827.00	2.11	333.08	5,826.40	-3.39	-0.52	-2.36	0.28	-0.27	-1.39
5,922.00	1.76	331.41	5,921.34	-0.55	-2.01	0.80	0.37	-0.37	-1.76
6,017.00	1.58	332.99	6,016.30	1.90	-3.31	3.53	0.20	-0.19	1.66
6,112.00	2.55	334.57	6,111.24	4.97	-4.81	6.88	1.02	1.02	1.66
6,206.00	2.68	334.01	6,205.14	8.84	-6.67	11.07	0.14	0.14	-0.60
6,301.00	2.29	321.83	6,300.05	12.33	-8.81	15.14	0.69	-0.41	-12.82
6,396.00	2.20	317.43	6,394.98	15.16	-11.22	18.86	0.20	-0.09	-4.63
6,494.00	2.29	332.82	6,492.90	18.29	-13.39	22.66	0.62	0.09	15.70
6,586.00	1.76	334.84	6,584.85	21.20	-14.83	25.84	0.58	-0.58	2.20
6,680.00	1.58	330.79	6,678.81	23.64	-16.07	28.53	0.23	-0.19	-4.31
6,775.00	2.52	350.55	6,773.75	26.84	-17.06	31.67	1.22	0.99	20.80
6,870.00	2.29	354.96	6,868.66	30.79	-17.57	35.10	0.31	-0.24	4.64
6,965.00	2.29	356.81	6,963.59	34.58	-17.84	38.26	0.08	0.00	1.95
7,060.00	1.76	354.26	7,058.53	37.93	-18.09	41.06	0.57	-0.56	-2.68
7,155.00	1.49	352.42	7,153.49	40.60	-18.40	43.37	0.29	-0.28	-1.94
7,249.00	1.49	359.01	7,247.46	43.04	-18.58	45.40	0.18	0.00	7.01
7,344.00	2.73	347.41	7,342.39	46.48	-19.10	48.44	1.37	1.31	-12.21
7,438.00	2.29	347.14	7,436.30	50.49	-20.00	52.17	0.47	-0.47	-0.29
7,533.00	2.02	347.93	7,531.23	53.98	-20.77	55.40	0.29	-0.28	0.83
7,628.00	1.76	354.79	7,626.18	57.07	-21.26	58.14	0.36	-0.27	7.22
7,723.00	1.54	6.01	7,721.14	59.79	-21.26	60.29	0.41	-0.23	11.81
7,818.00	1.24	8.72	7,816.11	62.08	-20.97	61.92	0.32	-0.32	2.85
7,913.00	0.79	35.31	7,911.10	63.63	-20.43	62.82	0.67	-0.47	27.99
8,008.00	0.90	346.76	8,006.09	64.89	-20.22	63.69	0.74	0.12	-51.11
8,103.00	0.97	346.26	8,101.08	66.40	-20.59	65.10	0.07	0.07	-0.53
8,198.00	1.14	2.00	8,196.06	68.12	-20.74	66.56	0.35	0.18	16.57
8,292.00	1.06	5.42	8,290.04	69.92	-20.63	67.91	0.11	-0.09	3.64
8,387.00	0.97	22.56	8,385.03	71.54	-20.24	68.95	0.33	-0.09	18.04
8,482.00	0.88	47.87	8,480.02	72.77	-19.39	69.41	0.44	-0.09	26.64
8,577.00	0.88	55.08	8,575.01	73.68	-18.25	69.43	0.12	0.00	7.59
8,673.00	1.06	70.02	8,670.99	74.41	-16.81	69.12	0.32	0.19	15.56

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 921-20F
Well: NBU 921-20F
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well NBU 921-20F
TVD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
MD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
8,767.00	0.97	101.40	8,764.98	74.55	-15.21	68.25	0.59	-0.10	33.38
8,862.00	0.88	107.55	8,859.97	74.17	-13.73	67.04	0.14	-0.09	6.47
8,957.00	0.88	133.13	8,954.96	73.45	-12.50	65.72	0.41	0.00	26.93
9,052.00	1.14	135.19	9,049.94	72.28	-11.30	64.06	0.28	0.27	2.17
9,146.00	1.32	139.98	9,143.92	70.79	-9.95	62.05	0.22	0.19	5.10
9,242.00	1.42	131.55	9,239.89	69.15	-8.35	59.78	0.23	0.10	-8.78
9,336.00	1.58	139.98	9,333.86	67.39	-6.64	57.34	0.29	0.17	8.97
9,431.00	1.49	144.47	9,428.83	65.38	-5.08	54.80	0.16	-0.09	4.73
9,526.00	1.32	144.73	9,523.80	63.48	-3.73	52.47	0.18	-0.18	0.27
9,621.00	1.06	147.45	9,618.78	61.85	-2.63	50.50	0.28	-0.27	2.86
9,715.00	0.79	136.73	9,712.76	60.64	-1.71	48.99	0.34	-0.29	-11.40
9,811.00	1.06	150.27	9,808.75	59.39	-0.82	47.45	0.36	0.28	14.10
9,905.00	1.23	147.37	9,902.73	57.78	0.15	45.59	0.19	0.18	-3.09
10,001.00	1.23	147.10	9,998.71	56.05	1.27	43.54	0.01	0.00	-0.28
10,095.00	1.06	136.29	10,092.69	54.57	2.42	41.67	0.29	-0.18	-11.50
10,190.00	0.97	130.75	10,187.68	53.41	3.63	40.00	0.14	-0.09	-5.83
10,285.00	1.37	128.48	10,282.66	52.18	5.13	38.11	0.42	0.42	-2.39
10,380.00	1.56	126.36	10,377.63	50.71	7.06	35.77	0.21	0.20	-2.23
10,475.00	1.67	127.33	10,472.59	49.10	9.21	33.18	0.12	0.12	1.02
10,570.00	1.76	130.23	10,567.55	47.32	11.42	30.42	0.13	0.09	3.05
10,664.00	2.02	138.67	10,661.49	45.15	13.62	27.35	0.40	0.28	8.98
10,759.00	2.11	142.18	10,756.43	42.51	15.79	23.93	0.16	0.09	3.69
10,854.00	2.29	143.67	10,851.36	39.60	17.99	20.29	0.20	0.19	1.57
10,948.00	2.29	145.61	10,945.29	36.53	20.16	16.54	0.08	0.00	2.06
11,043.00	2.37	146.05	11,040.21	33.34	22.33	12.68	0.09	0.08	0.46
11,138.00	2.46	145.78	11,135.13	30.02	24.58	8.69	0.10	0.09	-0.28
11,233.00	2.46	150.79	11,230.04	26.56	26.72	4.64	0.23	0.00	5.27
LAST SDI MWD PRODUCTION SURVEY									
11,292.00	2.46	150.79	11,288.98	24.35	27.95	2.13	0.00	0.00	0.00
SDI PROJECTION TO BIT									

Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
2,825.00	2,824.92	8 5/8"	8.625	11.000

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N
Site: NBU 921-20F
Well: NBU 921-20F
Wellbore: OH
Design: OH

Local Co-ordinate Reference: Well NBU 921-20F
TVD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
MD Reference: GL 4792 & KB 19 @ 4811.00ft (PIONEER 54)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Design Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
184.00	184.00	-0.05	0.78	FIRST SDI MWD SURFACE SURVEY
2,808.00	2,807.92	-1.08	0.29	LAST SDI MWD SURFACE SURVEY
2,890.00	2,889.92	-0.64	0.30	FIRST SDI MWD PRODUCTION SURVEY
11,233.00	11,230.04	26.56	26.72	LAST SDI MWD PRODUCTION SURVEY
11,292.00	11,288.98	24.35	27.95	SDI PROJECTION TO BIT

Checked By: _____ Approved By: _____ Date: _____